

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-10082-00-00
Spot: SESESW Sec/Twnshp/Rge: 17-32S-12W
330 feet from S Section Line, 2970 feet from E Section Line
Lease Name: FORSYTH UNIT Well #: 3-2
County: BARBER Total Vertical Depth: 4510 feet

Operator License No.: 3372
Op Name: DIXON ENERGY, INC.
Address: 8100 E 22ND N BLDG 300, STE 200
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4550	2000	WITH 90 SX CMT
SURF	8.625	205		WITH 100 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/05/2009 4:45 PM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: SAND TO 4380' WITH 5 SX CMT. PLUG AT 630' WITH 15 SX GEL, 200# HULLS, & 50 SX CMT. PLUG AT 240' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.
146.58

Plugging Proposal Received By: JERRY W. STAPLETON Witness Type: NONE
Date/Time Plugging Completed: 03/05/2009 5:45 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 4385' & PUT 5 SX CMT ON TOP OF SAND BRIDGE. LAID CASING DOWN & RUN 2 3/8" TBG IN TO PLUG WITH. 1ST PLUG AT 630' WITH 15 SX GEL & 50 SX CMT W/100# HULLS. 2ND PLUG AT 240' WITH 50 SX CMT W/100# HULLS. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4435	4455		

INVOICED

DATE 5-15-09
INV. NO. 2009061398

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 27 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
MAR 11 2009
KCC DODGE CITY

PKT