

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-019-22484-00-00  
Spot: SWSWNW Sec/Twnshp/Rge: 12-34S-10E  
2970 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: LEGRAND Well #: 1A  
County: CHAUTAUQUA Total Vertical Depth: 1550 feet

Operator License No.: 31124  
Op Name: DOTY, TIM  
Address: PO BOX 117  
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1550		
SURF	8.625	40		

50.38

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/12/2009 8:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: \_\_\_\_\_ Company: \_\_\_\_\_ Phone: \_\_\_\_\_

Proposed Plugging Method: 50' plug at TD, 50 plug at 900' and 500' to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/13/2009 12:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

RAN 1" TO 1520' AND GELLED HOLE. PUMPED 5 SACKS OF CEMENT AND PULLED UP TO 900' AND PUMPED 5 MORE SACKS OF CEMENT. PULLED UP TO 500' AND CIRCULATED CEMENT TO TOP. PULLED 1" OUT AND TOPPED WELL OFF. A TOTAL OF 60 SACKS OF CEMENT WERE USED TO PLUG THIS WELL. WELL WAS CUT OFF AND LOCATION RESTORED.

Perfs:

RECEIVED  
KCC DISTRICT #3

MAR 16 2009 DAS

CHANUTE, KS

INVOICED

DATE 4-15-09  
INV. NO. 2009061399

RECEIVED  
KANSAS CORPORATION COMMISSION

MAR 26 2009


CONSERVATION DIVISION  
WICHITA, KS

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

PKT