

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-187-20227-00-00
Spot: NWSE Sec/Twnshp/Rge: 35-29S-41W
1980 feet from S Section Line, 1980 feet from E Section Line
Lease Name: CULLERS HL Well #: 1
County: STANTON Total Vertical Depth: 3086 feet

Operator License No.: 5952
Op Name: BP AMERICA PRODUCTION COMPANY
Address: 2225 W OKLAHOMA AVE
ULYSSES, KS 67880

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2130		
PROD	5.5	3086	0	WITH 750 SX CMT 100.30
SURF	8.625	628		WITH 400 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 03/04/2009 9:00 AM
Plug Co. License No.: 32721 Plug Co. Name: ELDREDGE WELL SERVICE LLC
Proposal Rcvd. from: KEVIN STRUBE Company: BP AMERICA PRODUCTION Phone: (620) 356-1237

Proposed Plugging Method: CIBP @ 2130'. TBG IN HOLE TO 2100'. FILL 5 1/2" WITH CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/04/2009 11:30 AM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

CIBP @ 2130'. PUMP 187 SX CMT FROM 2130' TO SURFACE. PUMPED 4 SX CMT INTO 5 1/2" ANNULUS. PRESSURED TO 500 PSI.

Perfs:

Top	Bot	Thru	Comments
2226	2234		
2170	2184		
2158	2162		

INVOICED
DATE 4-15-09
NV. NO. 2009061394
RECEIVED
KANSAS CORPORATION COMMISSION
MAR 27 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY HALLIBURTON.

Plugged through: TBG

District: 01

Signed Jack MacLaskey
(TECHNICIAN)

RECEIVED
MAR 10 2009
KCC DODGE CITY

Form CP-2/3

[Handwritten signature]