

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-19276-00-01
Spot: SWSWNW Sec/Twnshp/Rge: 3-9S-18W
2970 feet from S Section Line, 4950 feet from E Section Line
Lease Name: WILDRIX Well #: 1
County: ROOKS Total Vertical Depth: 1140 feet

Operator License No.: 8914
Op Name: H & C OIL OPERATING INC.
Address: PO BOX 86
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1140	0	400 SX
SURF	8.625	286	0	225 SX

37.05

Well Type: SWD UIC Docket No: D21094.0 Date/Time to Plug: 03/26/2009 8:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: CHARLIE RAMSEY Company: H&C OIL OPERATING, INC. Phone: (785) 434-7434

Proposed Plugging Method: Ordered out 150 sxs 60/40 pozmix - 4% gel - 300# hulls.
Cleaned out to 900'. Iron sulfide and sand.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/26/2009 10:30 AM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 1018'. Allied pumped 50 sxs cement with 100# hulls.
Pulled tubing to 890'. Allied pumped 90 sxs cement with 200# hulls - cwc.
PTOH. Topped off with 10 sxs cement - casing full.
Backside instant 200#.

Perfs:

Top	Bot	Thru	Comments
1030	1060		Cedar Hills

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 27 2009
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Richard Williams

(TECHNICIAN)

CM

Form CP-2/3

MAR 26 2009

PKT

CITIES SERVICE OIL CO.

#1

WILDRIX

23

3-9-18W
SW SW NW

Contr. J. W. BRADEN DRUG. CO.

ROOKS

County

E 1984 Comm. Comp. 9-2-49 IP 160 BO & 68 BWPD
PHY POT

Tops	Depth	Datum
HEEB	3126	- 1142
DODGE	3147	- 1163
LANS	3165	- 1181
T.D.	3370	- 1386

8" 286 PB 3314
 5" 3370 PERF 3338-53
 ACID 500
 RMP 150 BO/20 HRS

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS

