

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-01840-00-01  
Spot: NWNWNW Sec/Twnshp/Rge: 6-10S-23W  
4950 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: GANO Well #: 5  
County: GRAHAM Total Vertical Depth: 4026 feet

Operator License No.: 5285  
Op Name: HANSEN, DANE G. - TRUST  
Address: PO BOX 187  
LOGAN, KS 67646

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4025	0	w/unknown sxs cmt
SURF	8.625	207	0	w/unknown sxs cmt <u>130.85</u>

Well Type: EOR UIC Docket No: E13102.2 Date/Time to Plug: 03/10/2009 10:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: RICHARD WALGREN Company: HANSEN, DANE G. - TRUST Phone: (785) 689-4816

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 4% gel - 300# hulls.  
Three drill collars at 3842' - 3940'.  
Note: Well currently has pending application for SWD - has been denied.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/10/2009 12:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

01/13/2009 - Ran tubing to 3842' - pumped 50 sxs of standard cement - 2% cc and 225# hulls.  
Tagged plug at 3348' - pumped 150 sxs 60/40 pozmix - 4% gel.  
Pulled tubing to 1984' and circulated approximately 30 sxs to the pit.  
03/10/2009 - Ran tubing to 1950' - pumped 180 sxs 60/40 pozmix - 4% gel to circulate to surface.  
Pulled all tubing. Topped off 5 1/2" casing with 20 sxs 60/40 pozmix - 4% gel.

Perfs:

INVOICED  
DATE 4-16-09  
INV. NO. 2009061405

RECEIVED  
MAR 20 2009  
KCC WICHITA

Remarks: SWIFT SERVICES CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Pat Bedore  
(TECHNICIAN)

CM

Form CP-2/3

MAR 12 2009

PACT

D G HANSEN

#5

GANO

6-10-23W  
NW NW NW

Contr. C-G DRLG

GRAHAM

County

E.2455RB Comm. 5-8-61

Comp. 7-28-61

IP 85 BOPD/LANS

Tops	Depth	Datum
ANH	2066	+389
TOP	3542	-1087
HEEB	3754	-1299
TOR	3777	-1322
KC	3794	-1339
B/KC	4020	-1565
TD	4026	-1571

Casing

8" 207

5" 4025

DST 3818-42/1 HR, 2235' SW, BHP 1315-1260/  
 /20": DST 3858-70/90", 360' C, 122' HG &  
 OCM, 120' CCO, 240' SW, BHP 1205-1140//20"  
 DST 3938-56/1 HR, 660' C, 790' GSY O,  
 BHP 565-530//: DST 3952-75/1 HR, 1140' C,  
 90' H G & OCM, 480' GSY O, BHP 670-610/  
 DST 3974-94/1 HR, 2565' SW, BHP 1340-1325/  
 PERF 3961-69: ACID 750: 5.7 BOPH: PERF  
 3946-54: ACID 1500: 2 BOPH/5 HRS: AVE 3.42  
 BOPH, NW: CO

HOOF NW POOL


INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS