

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20949-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 23-14S-13W
330 feet from S Section Line, 4950 feet from E Section Line
Lease Name: BOND Well #: 1
County: RUSSELL Total Vertical Depth: 3182 feet

Operator License No.: 33813
Op Name: JASON OIL COMPANY, LLC
Address: 3718- 83RD ST PO BOX 701
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3182	0	125 COM 2% GEL 3% CC
SURF	8.625	255	0	180 COM 2% GEL 3% CC

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/16/2009 2:00 PM
Plug Co. License No.: 32528 Plug Co. Name: FUNK, DAVID A. DBA OIL AND OPERATING SERVICES
Proposal Rcvd. from: DAVID FUNK Company: JASON OIL COMPANY, LLC Phone: (785) 324-1041

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 500# hulls - 6 sxs gel.

103.42

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 03/16/2009 4:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Ran tubing to 2200' - pumped 6 sxs gel - 75 sxs cement with 400# hulls.
Pulled tubing to 1450' - pumped 150 sxs cement with 100# hulls - cement circulated.
Pulled tubing out - filled casing with 10 sxs cement.
Hooked to Braden head.
Max. P.S.I. 200#.

INVOICED
DATE 4-16-09
INV. NO. 2009061406

RECEIVED
MAR 20 2009
KCC WICHITA

Remarks: QUALITY OILWELL CEMENTING COMPANY-TICKET #3189.

Plugged through: TBG

District: 04

Signed

Ray A Dinkel

(TECHNICIAN)

CM

Form CP-2/3

MAR 18 2009

PT

RALPH TITTEL
 BOX 526, RUSSELL, KS.

#1 BOND

23-14-13W
 SW SW SW

CONTR REVLIN DR LG., INC.

CTY RUSSELL

GEOL _____

FIELD HALL-GURNEY

E 1740 RB CM 9/1/76

CARD ISSUED 12/16/76

P 7 BOPD + 50 BOPD
 TARK 2267-77 & 2331
 -36, LKC 2901-04 &
 2920-24

+	+	+
+	+	+
+	+	+

API 15-167-20,949

SMP	TOPS	DEPTH	DATUM
SC	675	+1065	
GR HAVEN	2229	- 489	
1ST TARK SD	2241	- 501	
2ND TARK SD	2264	- 524	
TARK LS	2298	- 558	
TARK SD	2322	- 582	
TOP	2575	- 835	
HEEB	2810	-1070	
TOR	2829	-1089	
LKC	2878	-1138	
BKC	3141	-1401	
ARB	3178	-1438	
RTD	3183	-1443	

8-5/8" 255/180sx, 5 1/2" 3182/125sx
 DST (1) 2881-2930/30-30-30, 60' GIP,
 120' G&OCM, SIP 471-43# FP 79-105#
 MICT - PF (LKC) 8/2920-24, AC 1000, PF
 (LKC) 2901-94, AC 2200, SWB 2 1/2 BF, 20%
 OIL/1 HR, PF (TARK) 2331-36, FRAC 300
 BW + 1500 SD, PF 2267-77, FRAC 300 BW +
 1500# SD, SWB 20 BFPH, 40-70% OIL + GSE
 POP, PUMPING LD

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS