

15-195-22173-00-00

4-060834

TO: ✓
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

2-12

API Number: 15-195-22,173-00-00

N2 N2 SE /4 SEC. 02, 11 S, 24 W
2310 feet from S section line
1320 feet from E section line

Operator license# 5123

Lease: Hollandworth "A" Well # 1

Operator: Pickrell Drilling Company, Inc.

County: Trego

Address: 110 N. Market - Suite #205
Wichita, Kansas 67202

Well total depth 3915 ^{127.24} feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 228 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Pickrell Drilling Company, Inc. License# 5123

Address: Wichita, Kansas 67202

Company to plug at: Hour: P.M. Day: 12 Month: February Year: 1996

Plugging proposal received from: Doyle Folkerts

Company: Pickrell Drilling Company, Inc. Phone: 316-262-8427

Were: Order 190 sxs 60/40 posmix - 6% gel with 1/4# floseal per sack.
Space all plugs with heavy drilling mud through drill pipe.

RECEIVED
KANSAS CORP COM
2-21-1996
1996 FEB 21 A 11:10

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 9:30 P.M., Day: 12, Month: February, Year: 1996

Actual plugging report:

- 1st. Plug at 1925' w/25 sxs. - Anhydrite 1896' - 1937'
- 2nd. Plug at 1050' w/100 sxs. - Dakota 730' - 1030'.
- 3rd. Plug at 280' w/40 sxs. - Surface pipe to 228'.
- 4th. Plug at 40' w/10 sxs.
- Rathole with 15 sxs.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO

Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO

Plugged through TUBING , CASING . Elevation: 2330 GL

I did / did not observe the plugging.

Herb Deines
DH (agent)

DATE 2-28-96
INV. NO. 44903