

P

6 060236

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-195-20,783-00-00
C SE SE, SEC. 2, T 11 S, R 24 (W)
660 feet from N/S section line
660 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5135

Lease Name Littlechild Well # B-#1

Operator: John O. Farmer

County Trego

Name & Address W. Wichita

Well Total Depth 4010 130.33 feet

Russell, Ks. 67665

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 203

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XX

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 176, Chase, Ks. 67524

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19

Plugging proposal received from _____

(company name) _____ (phone) 316-938-2457

were: Order 165 sks 50/50 pozmix 6% gel 3% cal. cl. 25 sks gel, 5 sks hulls, 8 5/8" plug.

Elevation 2283 Anhy 1892

Plugging Proposal Received by [Signature]
(TECHNICIAN)

Plugging Operations attended by Agent?: All XX Part _____ None _____

Operations Completed: Hour: 2:30 PM Day: 23 Month: May Year: 19 84

ACTUAL PLUGGING REPORT 8 5/8" set at 203' w/170 sks 4 1/2" set at 3952' w/125 sks.

Top perf. @ 3827, plugged bottom w/4 sks cement, sand and 4 sks cement 3750'

P.B. to 3924' shot pipe 3 times and recovered 2515'. Pumped in 8 5/8". 4 hulls

25 cement, 10 gel, 70 cement, 15 gel, 1 hulls, plug, 70 cement w/700 pounds.

Remarks: _____
(if additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
6-4-1984
JUN 04 1984

INVOICED

DATE 6-5-84

INV. NO. 1805

Signed [Signature]
(TECHNICIAN)