

6 031052

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 1970

SW SW NE SEC. 3, T 11 S, R 24 W/E
2970 feet from S section line
2310 feet from E section line

Lease Name Ott Well # A-1

County Trego 128.51

Well Total Depth 3954 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 223

TECHNICIAN'S PLUGGING REPORT

Operator License # 04451

Operator: P. Todd Landes, Jr.

Name & Address

Box 867

Magnolia, Arkansas 71753

Abandoned Oil Well Gas Well Input Well SWD Well U&A

Other well as hereinafter indicated

Plugging Contractor Allied Cement Co. License Number

Address Russell, Kansas

Company to plug at: Hour: PM Day: 15 Month: March Year: 19 88

Plugging proposal received from Copeland Landes

(company name) P. Todd Landes, Jr. (phone)

were: 8 5/8" set at 223' w/160 sks cwc. 4 1/2" set at 3939' w/150 sks.

Perf 3716' - 3844'. Perf at 1050' for Dakota and 1900' for Anhy.

Order 250 sks ATL Cement Blend w/5 sks Hulls. Allied Cement Co.

Cheyenne Water Truck.

Plugging Proposal Received by Carl Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 5:00PM Day: 15 Month: March Year: 19 88

ACTUAL PLUGGING REPORT Squeeze 4 1/2" casing w/150 sks ATL Cement Blend w/5 sks Hulls mixed in. To Max Psi 600#. Close in Psi 300#. Squeeze 8 5/8" - 4 1/2" Annulus w/ 100 sks Cement Blend. Max Psi 600#. Close in 400# Psi. Plug complete.

RECEIVED
STATE CORPORATION COMMISSION

4-22-1988
APR 22 1988

Remarks: CONSERVATION DIVISION
(If additional description is necessary, use BACK of this report from Kansas)

(If you observe this plugging.

Signed Carl Goodrow
(TECHNICIAN)

Carl Goodrow

INVOICED

DATE 4-26-88

INV. NO. 20461