

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-20134-00-00  
Spot: CNWSE Sec/Twnshp/Rge: 3-11S-24W  
1980 feet from S Section Line, 1980 feet from E Section Line  
Lease/Unit Name: OTT Well Number: 1  
County: TREGO Total Vertical Depth: 3940 feet

Operator License No.: 30601 Conductor Pipe: Size \_\_\_\_\_ feet:  
Operator Name: NORTHSTAR INVESTMENTS, INC. Surface Casing: Size 8.62 feet: 208  
Address: 13735 PINNACLE Production: Size 4.5 feet: 3936 128.05  
WICHITA, KS 67230 Liner: Size \_\_\_\_\_ feet:

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 9/26/00 12:00:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (316) 278-2476

Proposed AS PER KCC RULES AND REGULATIONS.  
Plugging Order 200 sxs 60/40 pozmix - 10% gel - 500# hulls.  
Method: Order sand and common cement.

Plugging Proposal Received By: CARL GOODROW WitnessType: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 09/26/2000 10:00 AM KCC Agent: CARL GOODROW

**Actual Plugging Report:**

8 5/8" set at 208' w/150 sxs cwc. 4 1/2" set at 3936' w/200 sxs.  
Prod perms 3722' - 3755'. CIBP at 3738'.  
Sanded bottom back to 3670' w/4 sxs common cement on sand with bailer.  
Shots at 1500' - 1019' - 848'. Recovered 848' of 4 1/2" casing.  
Mixed and pumped 200 sxs cement blend with 500# hulls to Max. P.S.I. 1000#. Held. Plug complete.

RECEIVED  
STATE CORPORATION COMMISSION  
10-11-2000  
OCT 11 2000  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: ALLIED CEMENTING COMPANY

Plugged through:


District: 04

Signed Carl Goodrow  
(TECHNICIAN)

**INVOICED**  
DATE 10/16/00  
INV. NO. 2001060532

OCT 03 2000

LANDES EXPLOR. & SENTINEL RESOURCES #1 OTT 3-11-24W  
 MAGNOLIA, ARKANSAS C NW SE  
 Contr. HELLAR DRLG. CO., INC. Cty. TREGO  
 Geol. COPELAND LANDES Pool UNNAMED  
 E. 2335 KB Cm. 8/27/69 Cp. 10/23/69 IP PMP 43 BOPD, NW  
 GR 36.8/LKC 3722-30 & 3750-52  
 API 15-195-20,134



LOG Tops	Depth	Datum
ANH	1934	+ 401
TOP	3412	-1077
HEEB	3642	-1307
TOR	3664	-1329
LKC	3680	-1345
BKC	3906	-1571
LTD	3940	-1605

Csg. 8" 208/150 5X; 4 1/2" 3936/200  
 DST 3672-3700/40", 20' OCM, BHP  
 1139-889#/20", FP 26-35#  
 DST 3737-70/90", 150' GIP,  
 300' MGO, 1080' OCSW, BHP  
 1246-1246#/30", FP 71-960#  
 DST 3771-3791/2 1/2", 5' OIL, 440'  
 2, BHP 1308-1300#/45", FP  
 26-231#  
 DST 3798-3865/90", 120' GIP,  
 40' HO SP M, BHP 142-133#/  
 30", FP 53-53#  
 DST 3734-58/95", 420' GIP, 105'  
 OCM, 310' MGO, BHP 1301-  
 1281#/45", FP 36-179#  
 PF 3750-52; A 500' REC LD, SWB  
 5 BOPH/8 HRS 1500' OB, /3722-30  
 A 1500; REC LD SWB 10' BOPH. +  
 (OVER)

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS