

15-195-21838-00-00

4-110107

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-195-21,838-00-00

NW SE NE /4 SEC. 03, 11 S, 24 W
3630 feet from S section line
990 feet from E section line

Operator license# 30970

Lease: Ott Well # 1

Operator: Golden Oil Company
P.O. Box 861
Address: 2905 Barclay Drive
Hays, Kansas 67601

County: Trego 127.73

Well total depth 3930 feet
Conductor Pipe: inch @ feet
Surface pipe 8 5/8 Inch @ 200 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Golden Oil Company License# 30970

Address: P.O. Box 861 - Hays, Kansas 67601

Company to plug at: Hour: 9:00 A.M. Day: 24 Month: August Year: 2000

Plugging proposal received from: Ron Giest

Company: Golden Oil Company Phone: 785-628-1099

Were: Plug according to KCC Rules & Regulations.
Ordered 165 sxs 60/40 pozmix - 10% gel - 10sxs gel and 400# hulls

RECEIVED

STATE CORPORATION COMMISSION

8-31-2000

AUG 31 2000

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour: 10:00 A.M., Day: 24, Month: August, Year: 2000

Actual plugging report: 8 5/8" S.P. at 200' w/140 sxs cement. 4 1/2" casing at 3929' with 125 sxs cement. Perf at 1900' and circulated with 280 sxs cement. Tied to 4 1/2" casing and pumped 165 sxs cement and 10 sxs gel with 400# hulls. Tied to annulus - took no cement. Total of 165 sxs 60/40 pozmix with 10% gel - 10 sxs gel - 400# hulls. Anhydrite at 1935' to 1975'.

Remarks: Allied Cementing. Honas Tank - water.

Condition of casing(in hole): GOOD X BAD Anhy.plug: YES NO

Bottom plug(in place): YES, CALC, NO Dakota plug: YES, NO

Plugged through TUBING, CASING X Elevation: 2330 GL

I did [X] / did not [] observe the plugging.

Roger L. Moses
(agent)

Form CP-2/3

INVOICED
DATE 9/11/00
INV. NO. 2001060627

MB

SOUTHERN STATES OIL COMPANY

P.O. BOX 1365

#2 BAUGHER

23-12-21W
100'W, C NE NE SW

GREAT BEND, KS 67530

CONTR RAINS & WILLIAMSON

CTY TREGO

GEOL GREEN & GREEN

FIELD ELLIS NW

E 2315 KB CM 12/31/80 CARD ISSUED 3/26/81 IP

P 50 BOPD & WTR

2310 GL

ARB OH 4001-4010

API 15-195-20,696

+	+	+
+	+	+
+	+	+

SMP	TOPS	DEPTH	DATUM
ANH		1703	+ 612
TOP		3345	-1030
HEEB		3566	-1251
TOR		3589	-1274
LKC		3604	-1289
B KC		3836	-1521
MARM		3906	-1591
WEA ARB		3978	-1663
ARB		4000	-1685
RTD		4010	-1695

8 5/8" 243/200sx; 5 1/2" 4001/150sx

DST (1) 3362-3400/30-60-30-30, REC 20' M, SIP 742-707#, FP 45-36/54-45#

DST (2) 3504-3580/60-30-60-30, REC 85' M, SIP 1101-1056#, FP 54-72/90-98#

DST (3) 3562-3650/60-30-60-30, REC 97' SGCM, 20' SO SPKD M, SIP 152-143#, FP 81-90/98-116#

DST (4) 3717-3775/60-30-45-30, REC 110' SGO SPKD M, SIP 98-107#, FP 18-63/90-81#

DST (5) 3774-3840/30-30-45-30, REC 25' MW, SIP 233-98#, FP 54-54/63-45#

DST (6) 3999-4010/30-30-30-30, REC 360' GIP, 85' SGHOCM, 210' CL GO, SIP 1200-1191#, FP 18-54/81-116#

MICT - C9, (ARB OH), NAT POP,

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS