

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER 15-125- 01634-00-00  
NE SW SW Sec/Twp/Rge 2-31-16E  
946 (GPS) feet from south section line  
3984 (GPS) feet from east section line

35

TECHNICIAN'S PLUGGING REPORT

Operator License # 32596  
Operator: New Donna Lee Oil Company  
Name & 221 Fern Meadow Drive  
Address: Bakersfield, CA 93308  
AB oil well XXXXXX Gas Well \_\_\_\_\_

Lease/Well# Newman #09 (GPS)  
County Montgomery  
Well Total Depth 850 (est) feet  
Production Pipe: 2 Size Feet 850 (est)  
Surface Casing: 10 Size Feet NA  
SWD Well/ Input Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: Rick's Well Service Inc Lic. # ~~33422~~ 30849  
Address: PO Box 268, Cherryvale, Kansas 67335

Company to plug at: \_\_\_\_\_ Hour: \_\_\_\_\_ Day: 27 Month: 2 2006

Plugging proposal received from: Rick Housel

Company Name: Rick's Well Service Phone: 620-252-8656

Were: Clean well to TD and fill with cement.

Plugging Proposal Received by: Alan M. Dunning

Plugging attended by Agent: All \_\_\_\_\_ Part XXXXXX TECHNICIAN None \_\_\_\_\_

Operations Completed: Hour: \_\_\_\_\_ Day: 27 Month: 2 2006

Actual Plugging Report: The well was perforated at 350', 150' and 75'. A 1" cement string was then lowered to 850'. Gel was circulated and 20 sacks of cement spotted at TD. The cement string was raised to 350' and cement circulated to surface. A total of 132 sacks of portland cement were used to plug well.

**INVOICED**

RECEIVED  
KANSAS CORPORATION COMMISSION

DATE 4-17-09

INV. NO. 2009061410

APR 08 2009

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION  
WICHITA, KS

I partially observed this plugging

Signed:

Alan M. Dunning  
TECHNICIAN

PKA