

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
 Please TYPE Form and File ONE Copy

Form CP-1
 March 2009
This Form must be Typed
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 34038
 Name: Flatirons Resources LLC
 Address 1: 303 E. 17th Ave Suite 940
 Address 2: _____
 City: Denver State: CO Zip: 80203 + _____
 Contact Person: Jeffery Jones
 Phone: (303) 292-3902 ext 224

API No. 15 - 137-20500 -0000
 If pre 1967, supply original completion date: _____
 Spot Description: 33
-W2 W2 SE Sec. 12 Twp. 5 S. R. 24 East West
1,320 Feet from North / South Line of Section
2,310 Feet from East / West Line of Section
 Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
 County: Norton
 Lease Name: Farm & Ranch Reality Well #: 33-12

Check One: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: _____
 SWD Permit #: _____ ENHR Permit #: _____ Gas Storage Permit #: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks
 Surface Casing Size: 8 5/8" #23 Set at: 260 Cemented with: 180 common cement Sacks
 Production Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

List (ALL) Perforations and Bridge Plug Sets:

Elevation: 2326 (G.L. / K.B.) T.D.: 3970 PBTD: _____ Anhydrite Depth: 1950'
(Stone Corral Formation)

Condition of Well: Good Poor Junk in Hole Casing Leak at: _____
(Interval)

Proposed Method of Plugging (attach a separate page if additional space is needed):

Plug and abandon well per KCC orders w/Allied cementers 230 sx 60/40 POZ mix 4% gel 1/4 #flo seal per bbl 2-3% C.C.
 1st plug @ 3824' 25 sx, 2nd plug @ 1950' 25 sx, 3rd plug @ 1200' with 100 sx, 4th plug @ 300' w 40 sx, Rathole 30 sx

Is Well Log attached to this application? Yes No Is ACO-1 filed? Yes No

If ACO-1 not filed, explain why:

RECEIVED
KANSAS CORPORATION COMMISSION

APR 07 2009

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission CONSERVATION DIVISION

Company Representative authorized to supervise plugging operations: Jeffery Jones WICHITA, KS

Address: 303 E. 17th Ave Suite 940 City: Denver State: CO Zip: 80203 + _____

Phone: (785) 871-7331

Plugging Contractor License #: 33493 Name: American Eagle Drilling, LLC

Address 1: 700 S. Washington Address 2: P.O. Box 66

City: Plainville State: KS Zip: 67663 + _____

Phone: (785) 434-2079

Proposed Date of Plugging (if known): 12/12/08 100pm 1

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 4/6/09 Authorized Operator / Agent: _____
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

**well plugged - KCC - PKT*

*Dest 4
PKT*

Farm & Ranch Realty
#33-12

American Eagle Drilling, LLC
700 S. Washington
P. O. Box 66
Plainville, KS 67663
785-434-2079

DATE: 12-2-08 TIME: 2:30 AM/PM

Tool Pusher Signature: Don Morris

Spud Call:
Company Representative: Jeff Jones

Company Name: Flat Iron Resources LLC.

Spud Date: 12-2-08 KCC Representative: Martin Mills

Conductor Size: n/a inches set at n/a ft.

Surface Casing: Proposed setting depth 550' ft. Size 8 5/8 # 23 inches

Surface Casing: Minimum 200' ft. Alt I/II Set @ 260'

Drilling Fluid Mgmt. X Normal @ completion salt/completion Steel pits (Approved haul off pit)
303-292-3902 x224

Plugging:
P.O. received from: Jeff Jones. Phone # 303-809-3994

Drlg T.D. 4010 ft. Final T.D. 4011 ^{LTD} ft. Anhydrite: T 1934' B 1964'

Surface Casing: Size 8 5/8" # 23 set @ 260' ft. with 180 ^{37cc 2% gel} sacks of cement

Did cement circulate to surface? X Yes No

Did you rat hole ahead? 5' Yes No

1st. Plug Arbuckle @ 3824' ft. with 25 sacks of cement.

n/a Plug Hugoton/Council Grove @ n/a ft. with n/a sacks of cement.

2nd Plug Anhydrite/S.P. @ 1950' ft. with 25 sacks of cement.

3rd Plug Usable Water @ 1200' ft. with 100 sacks of cement.

4th Plug Fresh Water @ 300' ft. with 40 sacks of cement.

4th Plug Base Surface Casing @ 300' ft. with 40 sacks of cement

5th Plug Top of Surface Casing @ 40' ft. with 10 sacks of cement.

6th Circulate rat hole with 30 sacks of cement Circulate mouse hole with 10 sacks of cement

Water Supply Well: n/a Yes n/a No Who will plug? n/a

Cement: 60/40 POZ mix 5% gel 230 Sks 1/4 # flo seal per RR. 2-3% C. C.

Technician who gave plugging orders Case Morris Date 12-9-08

Start Time: 11:15 12:11 (AM/PM) Completion Time: 3:00 (AM/PM) Completion Date: 12-12-08

Cement Company Name: Allied Cement Co.

Set Pipe: T.D. n/a ft. Prod. Casing size: n/a inches set at n/a ft. with n/a sacks of cement. DV Tool/Port Collar set at n/a ft. Cemented with n/a sacks of cement. Did cement Circulate? n/a Yes n/a No If no, why? n/a

RECEIVED
KANSAS CORPORATION COMMISSION
APR 07 2009
CONSERVATION DIVISION
WICHITA, KS