

15-195-22173-00-00

STATE OF KANSAS  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

FORM CP-1 (3/92)

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File ONE Copy)

API # 15-195-22,173-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Pickrell Drilling Company, Inc. KCC LICENSE # 5123  
(owner/company name) (operator's)

ADDRESS 110 N. Market, Suite 205 CITY Wichita,

STATE Kansas ZIP CODE 67202 CONTACT PHONE # (316) 262-8427

LEASE Hollandworth "A" WELL# 1 SEC. 2 T. 11S R. 24 (East ~~West~~)

-N/2 - N/2 - SE SPOT LOCATION/QQQQ COUNTY Trego

2310 FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

1320 FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET# \_\_\_\_\_

CONDUCTOR CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 228'KB CEMENTED WITH 160 SACKS

PRODUCTION CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: \_\_\_\_\_

ELEVATION 2293/2298 T.D. 3915 PBTD \_\_\_\_\_ ANHYDRITE DEPTH 1896(+402)  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING P&A as follows: 25sx @ 1925', 100sx @ 1050', 40sx @ 280', 10sx @ 40', 15sx in rathole (total 190sx) of 60-40 poz, 6% gel w/1/4# Floseal per 100sx. Complete @ 9:30 PM on 2-12-96.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes IS ACO-1 FILED? Yes

If not explain why? \_\_\_\_\_

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Doyle Folkerts PHONE# (316) 793-5742

ADDRESS P.O. Box 1303 City/State Great Bend, Kansas 67530

PLUGGING CONTRACTOR Pickrell Drilling Co. Inc. KCC LICENSE # 5123

ADDRESS 110 N. Market, Suite 205 - Wichita, KS. PHONE # (316) 262-8427  
(company name) (contractor's)

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Complete @ 9:30 PM on 2-12-96.

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 2-19-96 AUTHORIZED OPERATOR/AGENT: \_\_\_\_\_

C. W. Sebits  
(signature)  
C. W. Sebits - President

RECEIVED  
KANSAS CORP COM  
FEB 26 9 33 AM '96  
2-26-1996