

ORIGINAL

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

CONFIDENTIAL

Form ACO-1
September 1999
Form Must Be Typed

Operator: License # 31885
Name: M&M Exploration, Inc.
Address: 60 Garden Center - Suite 102
City/State/Zip: Broomfield, Colorado 80020
Purchaser: _____
Operator Contact Person: Mike Austin
Phone: (303) 438-1991
Contractor: Name: Duke Drilling Co., Inc.
License: 5929

Wellsite Geologist: Mike Pollok
Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SIOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:
Operator: _____
Well Name: _____

Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back Plug Back Total Depth
 Commingled Docket No. _____
 Dual Completion Docket No. _____
 Other (SWD or Enhr.?) Docket No. _____

01-04-06 01-12-06 02-18-06
Spud Date or Date Reached TD Completion Date or Recompletion Date

API No. 15 - 007-22964-00-00
County: Barber County, Kansas
S/2. NW/4 NW/4 Sec. 15 Twp. 34 S. R. 15 East West
1000 feet from S / (circle one) Line of Section
600 feet from E / (circle one) Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE SE NW SW
Lease Name: Z Bar Well #: 15-4

Field Name: _____
Producing Formation: _____
Elevation: Ground: 1618' Kelly Bushing: 1631'
Total Depth: 5100' Plug Back Total Depth: _____
Amount of Surface Pipe Set and Cemented at 924 Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set _____ Feet
If Alternate II completion, cement circulated from _____
feet depth to _____ w/ _____ sx cmt.

Drilling Fluid Management Plan
(Data must be collected from the Reserve Pit) ALT I WITHIN 6-7-07
Chloride content _____ ppm Fluid volume 167 bbls
Dewatering method used Haul off to Disposal
Location of fluid disposal if hauled offsite: _____
Operator Name: OWoolsey Petroleum, Inc.
Lease Name: Clarke SWD License No.: 33168
Quarter SW Sec. 8 Twp. 32 S. R. 12 East West
County: Barber Docket No.: D-28492

RECEIVED
APR 10 2006

KCC WICHITA

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: Michael M Austin
Title: President Date: 4-10-06
Subscribed and sworn to before me this 7th day of April 2006
Notary Public: Stephen Paolini
Date Commission Expires: 12-13-2009
STEPHEN PAOLINI



KCC Office Use ONLY
 Letter of Confidentiality Attached
If Denied, Yes Date: _____
 Wireline Log Received
 Geologist Report Received
 UIC Distribution
KCC
APR 10 2006
CONFIDENTIAL

ORIGINAL

Operator Name: MGM Exploration, Inc. Lease Name: Z Bar Well #: 15-4
Sec. 15 Twp. 34 S. 15 East West County: Barber County, Kansas

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken Yes No
(Attach Additional Sheets)

Samples Sent to Geological Survey Yes No

Cores Taken Yes No

Electric Log Run Yes No
(Submit Copy)

List All E. Logs Run: Induction, Density-Neutron Microlog, Sonic

Log Formation (Top), Depth and Datum Sample

Name	Top	Datum
Penn	3042	-1411
Base Heebner	3958	-2327
Cherokee	4758	-3127
Miss	4792	-3161

CASING RECORD New Used

Report all strings set-conductor, surface, intermediate, production, etc.

Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacs Used	Type and Percent Additives
Conductor		20"		60'			
Surface	12-1/4"	8-5/8"	24#	924'	65/35 Class A	325 150	6%gel 3%cc 3%cc 2%gel
Production	7-7/8"	5-1/2"	15.5#	5098'	ASC	200	8#KolSeal 1/2#FloSeal

ADDITIONAL CEMENTING / SQUEEZE RECORD

Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate				
<input type="checkbox"/> Protect Casing				
<input type="checkbox"/> Plug Back TD				
<input type="checkbox"/> Plug Off Zone				


Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
	4784-4972 (70 holes)	2500 gals 15% MCA	4784-4972
		Frac 5800BW + 40,500 # sand	

TUBING RECORD Size 2 3/8 Set At 5024' Packer At _____ Yes No

Date of First, Resumed Production, SWD or Enhr. 02-18-2006 Producing Method Flowing Pumping Gas Lift Other (Explain)

Estimated Production Per 24 Hours Oil 0 Bbls. Gas 25 Mcf Water _____ Bbls. Gas-Oil Ratio _____ Gravity _____

Disposition of Gas Vented Sold Used on Lease (If vented, Sumit ACO-18.) Open Hole Perf. Other (Specify) _____ Commingled 4784-4972'



ALLIED CEMENTING CO., INC.

22936

Federal Tax I.D. **KCC**

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

APR 10 2006

SERVICE POINT:

MEDICINE LODGE

CONFIDENTIAL

DATE <u>1-13-06</u>	SEC. <u>15</u>	TWP. <u>34s</u>	RANGE <u>15W</u>	CALLED OUT <u>7:00 pm</u>	ON LOCATION <u>9:20 pm</u>	JOB START <u>1:00 am</u>	JOB FINISH <u>3:50 am</u>
LEASE <u>ZGAR</u>	WELL # <u>15-4</u>	LOCATION <u>160 & DEERHEAD RD., S To</u>			COUNTY <u>BARBER</u>	STATE <u>KS</u>	
OLD OR <u>NEW</u> (Circle one)			COTTAGE CREEK RD, 3/4 E, 1/2 N, 1/4 E, S/INTO				

CONTRACTOR DUKE #7
 TYPE OF JOB PRODUCTION CASING
 HOLE SIZE 7 7/8" T.D. 5,100'
 CASING SIZE 5 1/2" DEPTH 5,102'
 TUBING SIZE _____ DEPTH _____
 DRILL PIPE 4 1/2" DEPTH _____
 TOOL _____ DEPTH _____
 PRES. MAX 1,700 MINIMUM 100
 MEAS. LINE _____ SHOE JOINT 20'
 CEMENT LEFT IN CSG. 20'
 PERFS. _____
 DISPLACEMENT 122 1/2 bbl. 2% KCL WATER

OWNER M&M EXPLORATION
 CEMENT
 AMOUNT ORDERED 25 SX 60/46/6 (M&M USE)
200 SX ASC 18" KOL SEAL/SAK + .5% FL-160 + 1/2"
FLO-SEAL, 500 GAL. MUD CLEAN, 12 GAL. CLAPRO

EQUIPMENT
 PUMP TRUCK CEMENTER BILL A.
 # 360 HELPER DWAYNE W.
 BULK TRUCK
 # 381 DRIVER JASON K.
 BULK TRUCK
 # _____ DRIVER _____

COMMON	<u>15</u>	A.	@	<u>8.70</u>	<u>130.50</u>
POZMIX	<u>10</u>		@	<u>4.70</u>	<u>47.00</u>
GEL	<u>1</u>		@	<u>14.00</u>	<u>14.00</u>
CHLORIDE			@		
ASC	<u>200</u>		@	<u>10.75</u>	<u>2150.00</u>
Kol Seal	<u>1600</u>	#	@	<u>.60</u>	<u>960.00</u>
FL-160	<u>94</u>	#	@	<u>8.70</u>	<u>817.80</u>
FLO Seal	<u>100</u>	#	@	<u>1.70</u>	<u>170.00</u>
MudClean	<u>500</u>	gal	@	<u>1.00</u>	<u>500.00</u>
Clap Pro	<u>12</u>	gal	@	<u>24.10</u>	<u>289.20</u>
			@		
			@		
HANDLING	<u>299</u>		@	<u>1.60</u>	<u>478.40</u>
MILEAGE	<u>35 X 299 X</u>		@	<u>.00</u>	<u>627.90</u>
					TOTAL <u>6184.80</u>

REMARKS:

PIPE ON BOTTOM, BASKET CIRCULATION, PUMP PRE-FLUSH, PLUG RAT & MOUSE HOLES WITH 25 SX 60/46/6, PUMP 200 SX ASC + 8" KOL SEAL/SAK + .5% FL-160 + 1/2" FLO-SEAL, STOP PUMPS, WASH PUMP & LINES, RELEASE PLUG, START DISPLACEMENT, SEE LIFT, SLOW RATE, BUMP PLUG, FLOAT HEAD, DISPLACED WITH 122 1/2 bbl. 2% KCL WATER.

SERVICE

DEPTH OF JOB	<u>5,102'</u>		
PUMP TRUCK CHARGE			<u>1510.00</u>
EXTRA FOOTAGE		@	
MILEAGE	<u>35</u>	@	<u>5.00</u> <u>175.00</u>
MANIFOLD HEAD RENT		@	<u>75.00</u> <u>75.00</u>
		@	
		@	

CHARGE TO: M&M EXPLORATION
 STREET _____
 CITY _____ STATE _____ ZIP _____

RECEIVED

APR 10 2006

TOTAL 1760.00

KCC WICHITA

PLUG & FLOAT EQUIPMENT

5 1/2" AFU FLOAT SHOE	<u>1</u>	@	<u>263.00</u>	<u>263.00</u>
3 1/2" LATCH DOWN PLUG	<u>1</u>	@	<u>350.00</u>	<u>350.00</u>
5 1/2" BASKET	<u>1</u>	@	<u>140.00</u>	<u>140.00</u>
5 1/2" TURBO LIZERS	<u>8</u>	@	<u>60.00</u>	<u>480.00</u>
		@		

TOTAL 1233.00

To Allied Cementing Co., Inc.
 You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

ANY APPLICABLE TAX WILL BE CHARGED UPON INVOICING

TAX _____
 TOTAL CHARGE _____
 DISCOUNT _____ IF PAID IN 30 DAYS

SIGNATURE Alan Vratil

ALAN VRATIL

PRINTED NAME

ALLIED CEMENTING CO., INC.

22931

Federal Tax ID
KCC

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

APR 10 2006

SERVICE POINT:
MEDICINE LODGE

DATE 1-4-06	SEC. 15	TWP. 34s	RANGE 15w	CONFIDENTIAL	CALLED OUT 6:00 pm	ON LOCATION 7:40 pm	JOB START 10:30 pm	JOB FINISH 11:40 pm
LEASE ZAA	WELL # 15-4	LOCATION ACTNA RD & 160, S TO COTTAGE			COUNTY BARBER	STATE KS		
OLD OR NEW (Circle one)				LOCATION CRACK RD, 3/4, 1/2 N TO CORRAL, 1/4 E, S INTO				

CONTRACTOR **DUKE #7**

TYPE OF JOB **SURFACE CASING**

HOLE SIZE **12 1/4"** T.D. **930'**

CASING SIZE **8 5/8"** DEPTH **923'**

TUBING SIZE DEPTH

DRILL PIPE **4 1/2"** DEPTH

TOOL DEPTH

PRES. MAX **800** MINIMUM **100**

MEAS. LINE SHOE JOINT **43.10'**

CEMENT LEFT IN CSG. **43.10'**

PERFS.

DISPLACEMENT **55 1/2 bbl. FRESH WATER**

OWNER **M&M EXPLORATION**

CEMENT

AMOUNT ORDERED **325 sk 6.5' 35' 6" + 3% cc + 1/4" FLO-SEAL, 150 sk CLASS A + 3% cc + 2% GEL**

COMMON	150 A	@	8.70	1305.00
POZMIX		@		
GEL		@		
CHLORIDE	16	@	38.00	608.00
ASC		@		
	ALW 325	@	8.15	2648.75
	Flo Seal 81"	@	1.70	137.70
		@		
		@		
		@		
		@		
HANDLING	511	@	1.60	817.60
MILEAGE	35 X 511 X .06			1073.10
				TOTAL 6590.15

EQUIPMENT

PUMP TRUCK CEMENTER **BILL M.**

414 HELPER **DENNIS C.**

BULK TRUCK

356 DRIVER **GREG K.**

BULK TRUCK

397 DRIVER **THOMAS D.**

REMARKS:

PIPE ON BOTTOM, ANNAK CIRCULATION PUMP PRE-FLUSH, PUMP 325 sk 6.5' 35' 6" + 3% cc + 1/4" FLO-SEAL, 150 sk CLASS A + 3% cc + 2% GEL, STOP PUMPS, ROZASO PLUG, START DISPLACEMENT, SEE LIFT, SLOW RATE, BUMP PLUG, FLOAT HEAD, CIRCULATED CEMENT, DISPLACED WITH 55 1/2 bbl. FRESH WATER.

SERVICE

DEPTH OF JOB **923'**

PUMP TRUCK CHARGE **0-300'** **670.00**

EXTRA FOOTAGE **623'** @ **.55** **342.65**

MILEAGE **35** @ **5.00** **175.00**

MANIFOLD **HEAD RENT** @ **75.00** **75.00**

RECEIVED

CHARGE TO: **M&M EXPLORATION**

STREET _____

CITY _____ STATE _____ ZIP _____

APR 10 2006

TOTAL **1262.65**

KCC WICHITA

PLUG & FLOAT EQUIPMENT

8 5/8" RUBBER PLUG	1	@	100.00	100.00
8 5/8" AICU INSERT	1	@	325.00	325.00
8 5/8" BASKETS	2	@	180.00	360.00
8 5/8" GUIDE SHOE	1	@	235.00	235.00
				TOTAL 1020.00

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

ANY APPLICABLE TAX WILL BE CHARGED UPON INVOICING

TOTAL CHARGE _____

DISCOUNT _____ IF PAID IN 30 DAYS


SIGNATURE **Alan Vratil**

ALAN VRATIL
PRINTED NAME

entered!

Koda Services, Inc.

Conductor and Rat Hole Drilling, Landfill Gas Drilling and Well Construction Nationwide



71020
B

Invoice

DATE	INVOICE #
1/12/2006	4224

BILL TO
M & M Exploration 3173 West 11th Ave. Dr Broomfield, CO 80020

KCC
APR 10 2006
CONFIDENTIAL

ORDERED BY	TERMS	DUE DATE	FIELD...	LEASE	LEGAL DESCRIPTION & CO...
Allan	Net 30	2/11/2006	1282	Z Bar # 15-4	Sec. 15-34S-15W; Barber Co

QUANTITY	DESCRIPTION	AMOUNT
60	Drilled 60' of 30" conductor hole	0.00T
1	Furnished 60' of 20" conductor pipe	0.00T
	Furnished 5' X 5' tinhorn	0.00T
	Dirt removal	
	Furnished welder & materials	
	Furnished grout	
	Drilled rat & mouse holes	
	Drilling services	2,600.00
	Taxable materials	4,450.00
	Kansas sales tax	235.85T
	County Tax	44.50
	Ins & Fuel Surcharge	564.00
	non taxable	0.00

RECEIVED
APR 10 2006
KCC WICHITA

Thank you for your business.	Total \$7,894.35
------------------------------	-------------------------