

State of Kansas



15-195-19034-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 10 1967
6-19-1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Ralph Glenn of Glenn & Smith Pipe Pulling is this
date requested permission to plug the following described well:

Mr. Glenn guarantees payment of the plugging fee.

Operator's full Name: John P. Jennings,

Complete Address: Union Center, Wichita, Kansas.

Lease Name: Galloway Well No. 1

Location: SE-SW-SW Sec. 10 Twp. 11 Rge. (E)(W)23

County Trego Total Depth 3710 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Glenn was instructed to plug the well as follows:

210'--7" OD Surface pipe, cement circulated with 115 Sx. (6 1/2 hole).

3709'--4 1/2" Production casing cemented with 150 Sx. No plug

Back, no perforations. Open hole completion.

Pull 4 1/2" casing and squeeze well with 20 Sx. gel using 3 sacks

hulls in initial gel and follow with 50 Sx. cement.

Very truly yours,

M. L. Nichols
Conservation Division Agent