

State of Kansas



15-195-19035-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
9-12-1966  
SEP 12 1966

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Herman Barnett of Leben Drilling, Inc., has this date requested permission to plug the following described well:

Mr. Barnett guarantees payment of the plugging fee.

Operator's full Name: Martin & Keller,

Complete Address: 1035 Kennedy Building, Tulsa, Oklahoma.

Lease Name: Heckman Well No. 1

Location: NW-NW-SW Sec. 11 Twp. 11 Rge. (E)(W) 23

County Trego Total Depth 3732 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Barnett was instructed to plug the well as follows:

207'--8 5/8" Surface pipe, cement circulated with 175 Sx.  
3731'--4 1/2" Production casing cemented on bottom with 100 Sx.  
Stage collar @ 1691' and filled to 300' with cement. Well  
plugged back to 3700'. Top perforation @ 3654'.

Push plug to 3640', set 10' sand bridge and set 3 Sx. cement  
with dump bailer. Push plug to 540', set 15' sand bridge and  
fill to bottom of cellar with Redi-Mix.

Very truly yours,

Conservation Division Agent