



15-195-20140-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 6 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Warren Davis of Hellar Drlg. Co., Inc., has this date requested permission to plug the following described well:

Mr. Davis guarantees payment of the plugging fee.

Operator's full Name: Landes Explor. Co. & Franks Petr. Co.,

Complete Address: P. O. Box #867, Magnolia, Arkansas.

Lease Name: Heckman Well No. 1

Location: SW-SE-SE Sec. 11 Twp. 11 Rge. (E)(W) 23

County: Trego Total Depth 3558' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Davis was instructed to plug the well as follows:

218'--8 5/8" Surface casing, cement circulated with---
Top of Dakota section @ 615'.

Circulate hole with heavy mud. Pull DP to 840' and displace 100 Sx.
cement thru DP. Pull DP to 245' and displace 20 Sx. cement thru Dp.
Pull DP, set bridge @ 40' With 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent