



15-195-20138-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
OCT 7 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Jim Lahar of B & B Drilling, Incorporated, has this date requested permission to plug the following described well:

Mr. Lahar guarantees payment of the plugging fee.

Operator's full Name: Okmar Oil Company.

Complete Address: 1130 Wichita Plaza Building, Wichita, Kansas.

Lease Name: Carpenter Well No. 2

Location: CSW-SW Sec. 13 Twp. 11 Rge. (E)(W) 23

County: Trego Total Depth 3794' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Lahar was instructed to plug the well as follows:

231'--8 5/8" Surface casing, cement circulated with 145 Sx.
Top of Dakota section @ 650'.

Circulate hole with heavy mud. Pull DP to 825' and and displace 100 Sx.
cement thru DP. Pull DP to 245' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

W. L. Nichols
Conservation Division Agent