

State of Kansas



15-195-20284-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 P. O. Box 17027 3830 S. Meridian  
 WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 10-10-1974  
 OCT 10 1974  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Red Bishop of Rains & Williamson Oil Co., has this date requested permission to plug the following described well:

Mr. Bishop guarantees payment of the plugging fee.

Operator's full Name: Rains & Williamson Oil Company, Incorporated,

Complete Address: 435 Page Court, 320 West Douglas, Wichita, Kansas.

Lease Name: Elmer M. LaRue Well No. 1

Location: SE-SW-SE Sec. 32 Twp. 11 Rge. (E)(W) 23

County: Trego Total Depth 4000' Oil Well

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Bishop was instructed to plug the well as follows:

247'--8 5/8" Surface casing, cement circulated.  
Top of Dakota section @ 675'.

Circulate hole with heavy mud. Pull DP to 900' and displace 110 Cu. Ft. cement thru DP. Pull DP to 275' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

M. L. Diebold  
 Conservation Division Agent