

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Oil Producers of Kansas, Inc.
Address: 1710 Waterfront Parkway, Wichita, KS 67201
Phone: (316) 681-0231 Operator License #: 8061
Type of Well: Oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: _____ (Date)
by: Jeff Klock (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Mississippi Depth to Top: 4372 Bottom: 4378 T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

077

API Number: 15-~~007~~-20, 1710001
Lease Name: Kirkpatrick OWWO
Well Number: 1
Spot Location (QQQQ): _____ - SW - SW - NE
2970 Feet from North / South Section Line
2310 Feet from East / West Section Line
Sec. 10 Twp. 31 S. R. 9 East West
County: Harper
Date Well Completed: 7-75
Plugging Commenced: 3-11-09
Plugging Completed: 3-13-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	254	
				4 1/2	4447	2080


RECEIVED
KANSAS CORPORATION COMMISSION
MAR 31 2009
CONSERVATION DIVISION
WICHITA, KS

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Blew gas down, unhooked well head, changed over for tubing, pulled tubing out, pumped 50 bbls water down casing to kill well, well was still gasing, pumped 25 sacks, 100# hulls down 4 1/2" casing, max pressure 900, shut in 600 psi, dug cellar, unpacked casing head, set floor, tagged cement at 4275', pulled slips, ripped casing at 2810', worked pipe, ripped 2640', worked pipe, ripped casing at 2420', worked pipe, ripped 2250', worked pipe, ripped 2080', pipe came free, pulled casing up to 1500', pumped 35 sacks 100# hulls, pulled to 1000', pumped 35 sacks, 100# hulls, pulled to 305', circulated cement with 95 sacks to surface, pulled rest of casing.

Name of Plugging Contractor: Quality Well Service, Inc. License #: 31925
Address: 190 US Highway 56, Ellinwood, KS 67526
Name of Party Responsible for Plugging Fees: Oil Producers of Kansas, Inc.

State of Kansas County, Sedgwick, ss.
Oil Producers Inc. of Kansas (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Signature]
(Address) 1710 Waterfront Parkway, Wichita, KS 67206
SUBSCRIBED and SWORN TO before me this 27th day of March, 2009
Loria A. Zehr My Commission Expires: May 5, 2010
Notary Public

[Handwritten initials]