

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

API No. 15 - 163-19276-00-01

Spot Description: _____

SW SW NW Sec. 3 Twp. 9 S. R. 18 ☐ East ☒ West

2,970 Feet from ☐ North / ☒ South Line of Section

4,950 Feet from ☒ East / ☐ West Line of Section

Footages Calculated from Nearest Outside Section Corner:

☐ NE ☐ NW ☒ SE ☐ SW

County: Rooks

Lease Name: Wildrix Well #: 1SWD

Date Well Completed: _____

The plugging proposal was approved on: 3/23/09 (Date)

by: Case Morris (KCC District Agent's Name)

Plugging Commenced: 3/26/09

Plugging Completed: 3/26/09

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8 5/8"	286'	None
		Production	5 1/2"	1140'	None

Run tubing to 1018' and plug with 50 sacks and 100# of hulls. Pull tubing to 890' and plug with 90 sacks with 200# of hulls. Cement circulated. Top off with 10 sacks down casing. Pressured backside and shut in at 200#. Total of 150 sacks of 60/40 posmix with 4% gel and 300# of hulls. Cementing

MAR 31 2009

CONSERVATION DIVISION
WICHITA, KS

Signature: Charles B. Ransaw

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202