

15-195-21247-00-00

Form CP-4
Rev. 12-15-80

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas. 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Trego SEC. 32 TWP. 11S RGE. 23W E/W
Location as in quarters or footage from lines:
N/2 SE SE

Locate Well
correctly on above
Section Platt.

Lease Owner Petroleum Management, Inc.
Lease Name LaRue #1 Well No. _____
Office Address P.O. Box H Plainville, Kansas 67663
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 11-16-83
Plugging completed 11-18-83
Reason for abandonment of well or producing formation Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Dennis Hammel
Producing formation _____ Depth to top _____ bottom _____ T.D. 4261'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	333'	none
				4-1/2"	4218'	3009'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Plugged off bottom with 4 sacks cement, sand to 4100' and 4 sacks cement. Shot casing
@3017' and pulled a total of 71 joints (3009') of 4-1/2" casing. Plugged well with
3 gel, 50 cement, 10 gel, 70 cement, 12 gel and 75 cement, 50/50 pos, 6% gel. Mixed
3 sacks hulls with the gel and cement.
Plugging Complete

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling


STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347, Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of November, 19 83

My Commission expires:



Irene Hoover
Notary Public
STATE CORPORATION COMMISSION
11-22-1983
NOV 22 1983

CONSERVATION DIVISION
Wichita, Kansas