


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Trego County. Sec. 35 Twp. 11S Rge. 23W (E) (W)
Location as "NE/CNW/SW" or footage from lines SW SW NE
Lease Owner Imperial Oil of Kansas, Inc.
Lease Name Howat Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed March 28, 1958
Application for plugging filed March 28, 1958
Application for plugging approved March 28, 1958
Plugging commenced March 28, 1958
Plugging completed March 28, 1958
Reason for abandonment of well or producing formation No commercial quantities of oil found.

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Leiker, 805 Main St. Victoria, Ks.
Producing formation Depth to top Bottom Total Depth of Well 3925 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	3-18-58	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

No. 1 plug set at 550 feet with 1/2 sack hulls and 25 sacks cement. No. 2 plug at 225' with 1/2 sack hulls and 15 sacks cement. No. 3 plug at 40 feet with 1/2 sack hulls and 10 sacks cement.

APR 22 1958
STATE CORPORATION COMMISSION

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Imperial Oil of Kansas, Inc.
Address 780 Fourth National Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Raymond L. Bacon (employee of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. IMPERIAL OIL OF KANSAS, INC.

(Signature) By: Raymond L. Bacon V-P
780 Fourth National Bldg., Wichita 2, Kansas (Address)

Subscribed and sworn to before me this 21st day of April, 1958

Louetta M. Duncan Notary Public.



PLUGGING
FILE SEC 35 T. 11 R. 23W
BOOK PAGE 91 LINE 23

15-195-00352-00-00

DRILLER'S LOG

Imperial Oil of Kansas, Inc.
780 Fourth National Bldg.
Wichita 2, Kansas

Howat No. 1
SW SW NE Sec. 35-11S-23W
Trego County, Kansas

Total Depth: 3925'

Elevation: 2435' RB
Production: D & A

Commenced: 3-18-58 Completed: 3-28-58

Contractor: Imperial Oil of Kansas, Inc.
Wichita, Kansas

Casing Record: Set 8-5/8" Surface Pipe at 225' with 150 sacks cement.

Figures indicate bottom of formations:

Sand & Shale	170'		<u>TOPS</u>	
Shale	225'			
Shale, Sand & Shells	1440'	Anhydrite	1867'	(- 568)
Shale & Shells	1867'	Heebner	3652'	(-1217)
Anhydrite	1910'	Toronto	3673'	(-1238)
Shale & Shells	2000'	Lansing	3687'	(-1252)
Shale	2265'	Rotary Total Depth	3925'	(-1490)
Shale & Shells	2375'			
Shale & Lime Streaks	2625'			
Shale & Lime	3634'			
Lime	3925'			
Total Depth	3925'			

We hereby certify this to be a correct and accurate log of the above described well as shown on the daily drilling reports.


RECEIVED
STATE CORPORATION COMMISSION
4-22-1958
APR 22 1958

IMPERIAL OIL OF KANSAS, INC.

By: Ray E. L. Rain
Vice-President

CONSERVATION DIVISION
Wichita, Kansas

Subscribed and sworn to before me this 21st day of April, 1958.



My Commission Expires:
December 19, 1960

Luetta M. Duncan
Notary Public

PLUGGING
FILE SEC 35-T-11 R234
BOOK PAGE 9/ LINE 23