

This form must be filed in triplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within five days after the completion of the well, regardless of how the well was completed. Circle one: Oil, gas, dry, SWD, OWWO, injection. Please type. Complete ALL sections. Applications must be filed for dual completion, commingling, salt water disposal and injection. Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.) KCC#-(316) 263-3238.


OPERATOR John O. Farmer, Inc. API NO. 15-195-20,905-00-00  
 ADDRESS P.O. Box 352 COUNTY Trego  
Russell, KS 67665 FIELD X Wildcat  
 \*\*CONTACT PERSON Margaret A. Schulte LEASE Walker  
 PHONE (913) 483-3144

PURCHASER \_\_\_\_\_ WELL NO. #1  
 ADDRESS \_\_\_\_\_ WELL LOCATION C SW SW  
660 Ft. from the south Line and  
660 Ft. from the west Line of  
 DRILLING CONTRACTOR John O. Farmer, Inc. the SW/4 SEC. 1 TWP. 11S RGE. 24W

ADDRESS P.O. Box 352  
Russell, KS 67665

PLUGGING CONTRACTOR John O. Farmer, Inc.  
 ADDRESS P.O. Box 352, Russell, KS 67665

TOTAL DEPTH 3900' PBTD \_\_\_\_\_  
 SPUD DATE 11-16-81 DATE COMPLETED 11-23-81  
 ELEV: GR 2288' DF 2291' KB 2293'



WELL PLAT  
 (Quarter)  
~~XXXXXX~~  
 Section -  
 Please  
 indicate.

DRILLED WITH ~~(CABLE)~~ (ROTARY) ~~(AIR)~~ TOOLS  
 Report of all strings set — surface, intermediate, production, etc. (New)/(Used) casing.

KCC \_\_\_\_\_  
 KGS \_\_\_\_\_  
 MISC. \_\_\_\_\_

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12-1/4"	8-5/8"	24	218'	Common	165	

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval


TUBING RECORD		
Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD	
Amount and kind of material used	Depth interval treated

RECEIVED  
 STATE CORPORATION COMMISSION  
 DEC - 1 1981  
 12-1-1981  
 CONSERVATION DIVISION  
 WICHITA, KANSAS

TEST DATE:		PRODUCTION			
Date of first production	Producing method (flowing, pumping, gas lift, etc.)	Oil	Gas	Water	Gas-oil ratio
		bbis.	MCF	%	bbis.
Disposition of gas (vented, used on lease or sold)				Producing interval (s)	CFPB

\*\* The person who can be reached by phone regarding any questions concerning this information.  
 A witnessed initial test by the Commission is required if the well produces more than 25 BOPD or is located in a Basic Order Pool.



Name of lowest fresh water producing stratum Unknown Depth 100'  
 Estimated height of cement behind pipe Top

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Clay Sand	0	50		Sample Tops
Blue Shale	50	218		
Shale & Sand	218	720	Anhydrite	(+395) 1898
Sand & Shale	720	1430	Heebner	(-1328) 3621
Sand	1430	1649	Toronto	(-1349) 3642
Red Bed	1649	1898	Lansing	(-1363) 3656
Anhydrite	1898	1941	B/KC	(-1604) 3897
Shale & Shell	1941	2110	T.D.	(-1607) 3900
Shale & Lime	2110	2360		
Lime & Shale	2360	2535		
Shale & Lime	2535	2880		
Lime & Shale	2880	3035		
Shale & Lime	3035	3290		
Lime & Shale	3290	3470		
Shale & Lime	3470	3680		
Lime	3680	3900		

DST #1 3810-50  
 Tool open 60-60-60-60 - weak blow  
 Rec: 118' gas  
       66' gas & oil cut mud  
 FP: 67-87  
 BHP: 135-135

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

A F F I D A V I T

STATE OF Kansas, COUNTY OF Russell SS,

John O. Farmer OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH, DEPOSES AND SAYS:

THAT HE IS president FOR John O. Farmer, Inc. OPERATOR OF THE Walker LEASE, AND IS DULY AUTHORIZED TO MAKE THIS AFFIDAVIT FOR AND ON BEHALF OF SAID OPERATOR, THAT WELL NO. #1 ON SAID LEASE HAS BEEN COMPLETED AS OF THE 30th DAY OF November 19 81, AND THAT ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

FURTHER AFFIANT SAITH NOT.

(S) John O. Farmer  
 John O. Farmer  
 November 30th DAY OF November 19 81

Margaret A. Schulte  
 NOTARY PUBLIC  
 Margaret A. Schulte



COMMISSION EXPIRES: January 27, 1985