

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-195-20168-00-00

API NUMBER _____

LEASE NAME OTT

WELL NUMBER 1A
2970'

SW NE Ft. from S Section Line

2310 Ft. from E Section Line

SEC. 3 TWP 11S RGE. 24W (E) or (W)

COUNTY TREGO

Date Well Completed 11/18/70

Plugging Commenced 3/15/88

Plugging Completed 3/15/88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div. SW
office within 30 days.

LEASE OPERATOR P. TODD LANDES, JR.

ADDRESS BOX 867, MAGNOLIA, AR 71753

PHONE# (501) 234-1866 OPERATORS LICENSE NO. 04451

Character of Well oil well being plugged

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on February 16, 1988 (date)

by Mr. Carl Goodrow - Hays, Kansas Office (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Lansing K-C Depth to Top 3716 Bottom 3914 T.D. 3940

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Dakota o-1010	Sand & Sh	0	223	8 5/8"	223	NONE
Permian 1010-3200	Lm & Shales	0	3939	4 1/2"	3939	NONE
Penn 3200-3914	Lm & Shales					
K C 3716-3914						
Oil Zones 3716, 3750, 3816, 3836, 3850						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Perforated @ 1050' below Dakota and at 1900' above Anny; Pumped down 4 1/2 with 150 sks econolite + 5 sacks hulls; pumped down annulus with 100 sks econolite.

(If additional description is necessary, use BACK of this form.)

RECEIVED

STATE CORPORATION COMMISSION

Name of Plugging Contractor P. T. LANDES, OPERATOR

License No. 04451

Address Box 867, Magnolia, Arkansas 71753

MAR 21 1988

STATE OF ARKANSAS COUNTY OF COLUMBIA, ss.

3-21-1988

CONSERVATION DIVISION

Wichita, Kansas

P. T. Landes, Jr. (Employee of Operator) of (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) P. T. Landes, Jr.

(Address) Box 867, Magnolia, AR 71753

SUBSCRIBED AND SWORN TO before me this 17th day of March, 19 88

My Commission Expires: November 16, 1989

De Ann Jones
Notary Public

