


15-195-20390-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission
245 North Water
Wichita, KS 67202

FORM CP-4

WELL PLUGGING RECORD



Locate well correctly on above
Section Plot

Trego County. Sec. 9 Twp. 11 Rge. 24 (E) W. (W)
Location as "NE/CN\W\SW2" or footage from lines C SE SE
Lease Owner Petroleum, Inc.
Lease Name Rt. 2 Garrett 'D' Well No. 1
Office Address Rt. 2, Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 11/29/76 19
Application for plugging filed 11/29/76 19
Application for plugging approved 11/29/76 19
Plugging commenced 11/29/76 19
Plugging completed 11/29/76 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Balthazor
Producing formation Depth to top Bottom Total Depth of Well 4000 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	207	8-5/8	yes	no

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1st plug @ 750' with 70 sacks 50-50 Poz 6% Gel
2nd plug @ 200' with 20 sacks
3rd plug @ 40' with 10 sacks
2 sacks in rathole
Job complete @ 2 a.m. 11/29/76
DEC 07 1976
12-7-1976
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Slawson Drilling Company, Inc.
Address 408 One Twenty Building, Wichita, Kansas 67202


STATE OF Kansas COUNTY OF Sedgwick SE.
James C. Remsberg (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James C. Remsberg
James C. Remsberg
408 One Twenty Building, Wichita 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of December 1976

My commission expires January 17, 1977

Mary Lou Taylor
Mary Lou Taylor Notary Public.



15-195-20390-00-00

DRILLERS LOG

OPERATOR Petroleum, Inc.
 Rt. 2
 Great Bend, Kansas 67530

LEASE Garrett 'D' No.1
 C SE SE Sec. 9-11S-24W
 Trego, County, Kansas

CONTRACTOR Slawson Drilling Company, Inc.
 408 One Twenty Building
 Wichita, Kansas 67202

COMMENCED 11/21/76

COMPLETED 11/29/76

RTD 4000'

CASING 200.76' new 8-5/8" set at 207' with 150 sx cement

0' to 212' 12½" Surface Hole
 212' to 845' Shale & Shells
 845' to 1366' Shale
 1366' to 1530' Shale & Shells
 1530' to 1747' Sand
 1747' to 1990' Shale & Shells
 1990' to 2033' Anhydrite
 2033' to 2451' Shale
 2451' to 2655' Shale & Lime
 2655' to 3790' Lime & Shale
 3790' to 4000' Lime
 4000' RTD

RECEIVED
 CONSERVATION COMMISSION
 12-07-1976
 DEC 07 1976
 CONSERVATION DIVISION
 WICHITA, KANSAS

STATE OF KANSAS
 COUNTY OF SEDGWICK

I, James C. Remsberg, of the Slawson Drilling Company, hereby state that the above and foregoing is a true and correct copy of the log of the Garrett 'D' No. 1 well.

James C. Remsberg
 James C. Remsberg

Subscribed and sworn to me on December 4, 1976

Mary Lou Taylor
 Mary Lou Taylor, Notary

My commission expires January 17, 1977

