

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Range Oil Company, Inc.
Address: 125 N. Market, Suite 1120 Wichita, KS 67202
Phone: (316) 265-6231 Operator License #: 5120
Type of Well: ENHR Docket #: E-26,708
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) *(If SWD or ENHR)*
The plugging proposal was approved on: 1-19-08 (Date)
by: _____ (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-035-23,625-00-01
Lease Name: Chase
Well Number: 4
Spot Location (QQQQ) W2 Approx - E/2 - NW - SE
1,980 Feet from North / South Section Line
1,780 Feet from East / West Section Line
Sec. 7 Twp. 33 S. R. 6 East West
County: Cowley
Date Well Completed: 10-24-85
Plugging Commenced: 1-19-09
Plugging Completed: 1-20-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	308'	none
				4 1/2	3119'	1114'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Gressel Oilfield Service placed 10 sacks of sand at bottom of casing across perfs and bailed five sacks of cement on top of sand. They pulled slips and cut surface casing off four feet below ground. Pulled stretch on casing and shot it off at 1114'. They pulled the casing up to 360 feet and circulated 150 sacks of cement to surface. Harrod welded a cap on surface casing and backfilled pit.

Name of Plugging Contractor: Gressel Oil Field Service, Inc. License #: _____
Address: 190 US Highway 56 Ellinwood, KS 67526
Name of Party Responsible for Plugging Fees: Range Oil Company, Inc.
State of Kansas County, Sedgwick, ss. _____
John M. Washburn (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

3004 KCC PET RECEIVED
34925 KANSAS CORPORATION COMMISSION
FEB 18 2009
CONSERVATION DIVISION
WICHITA, KS

(Signature) John M. Washburn
(Address) 125 N. Market, Suite 1120 Wichita, KS 67202

PEGGY L. SAILOR
Notary Public - State of Kansas
My Appt. Expires December 8, 2011

SUBSCRIBED and SWORN TO before me this 16th day of February, 2009
Peggy L. Sailor My Commission Expires: 12-08-11
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PT

COPELAND

POST OFFICE BOX 438
 HAYSVILLE, KS 67060
 (316) 524-1225
 (316) 524-1027 FAX

COPY

Acid & Cement

BURRTON, KS GREAT BEND, KS
 (620) 463-5161 (620) 793-3366
 FAX (620) 463-2104 FAX (620) 793-3536

INVOICE NUMBER:
 C33840-IN

BILL TO:
 RANGE OIL
 125 N MARKET #1120
 WICHITA, KS 67202

LEASE: CHASE 4 SWD

FEB 12 2009

DATE	ORDER	SALESMAN	ORDER DATE	PURCHASE ORDER	SPECIAL INSTRUCTIONS	
1/21/2009	C33840		1/20/2009		NET 30	
QUANTITY	U/M	ITEM NO./DESCRIPTION		D/C	PRICE	EXTENSION
1.00	EA	CEMENT PUMP CHARGE			600.00	600.00
150.00	SAX	60-40 POZ MIX 4 %			9.49	1,423.50
107.00	MI	CEMENT MILEAGE PUMP TRUCK			3.00	321.00
3.00	HR	OPERATOR CHARGE			75.00	225.00
150.00	EA	BULK CHARGE			1.25	187.50
706.20	MI	BULK TRUCK - TON MILES			1.10	776.82
1.00	EA	10% FUEL SURCHARGE			192.28	192.28
REMIT TO: P.O. BOX 438 HAYSVILLE, KS 67060		COP-B		Net Invoice:		3,726.10
		FUEL SURCHARGE IS NOT TAXABLE AND IS ADDED TO MILEAGE, PUMP AND OR DELIVERY CHARGES ONLY.		Sales Tax:		47.85
RECEIVED BY _____		NET 30 DAYS		Invoice Total:		3,773.95

RECEIVED
 KANSAS CORPORATION COMMISSION
 FEB 18 2009
 CONSERVATION DIVISION
 WICHITA, KS

There will be a charge of 1.5% (18% annual rate) on all accounts over 30 days past due.

Copeland Acid & Cement is a subsidiary of Gressel Oil Field Service, Inc.

Gressel Oil Field Service, Inc. reserves a security interest in the goods sold until the same are paid for in full and reserve all the rights of a secured party under the Uniform Commercial Code.