

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING APPLICATION**

Please TYPE Form and File ONE Copy

RECEIVED  
KANSAS CORPORATION COMMISSION  
APR 15 2009  
CONSERVATION DIVISION  
WICHITA, KS

Form CP-1  
March 2009

This Form must be Typed  
Form must be Signed  
All blanks must be Filled

Operator: License # 3842  
Name: LARSON ENGINEERING, INC.  
Address 1: 562 WEST STATE ROAD 4  
Address 2: \_\_\_\_\_  
City: OLMITZ State: KS Zip: 67564 + 8561  
Contact Person: TOM LARSON  
Phone: (620) 653-7368

API No. 15 - 167-23140-00-00  
If pre 1967, supply original completion date: \_\_\_\_\_  
Spot Description: C W/2 SE  
Sec. 10 Twp. 14 S. R. 15  East  West  
1320 Feet from  North /  South Line of Section  
1980 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: RUSSELL  
Lease Name: POLCYN "A" Well #: 1

Check One:  Oil Well  Gas Well  OG  D&A  Cathodic  Water Supply Well  Other: \_\_\_\_\_  
 SWD Permit #: \_\_\_\_\_  ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_

Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks  
Surface Casing Size: 8-5/8" Set at: 248' Cemented with: 150 Sacks  
Production Casing Size: 5-1/2" Set at: 3253.5' Cemented with: 200 Sacks

List (ALL) Perforations and Bridge Plug Sets:  
GORHAM SAND OH 3253.5-56.5' CIBP @ 3235' L-KC "G" 3109-12' L-KC "B" 3042-46'  
TORONTO 2985-89' PLATTS 2912-16' TOPEKA 2740-44'

Elevation: 1853' ( G.L. /  K.B.) T.D.: 3256.5' PBTD: 3235' Anhydrite Depth: 883'  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Junk in Hole  Casing Leak at: \_\_\_\_\_

Proposed Method of Plugging (attach a separate page if additional space is needed):

AS DIRECTED BY KCC. PORT COLLAR @ 892'. CEMENTED FROM 892' TO SURFACE W/ 105 SX 60/40 POZ W/ 6% GEL & 1/4#/SK FLOCELE.

Is Well Log attached to this application?  Yes  No Is ACO-1 filed?  Yes  No

If ACO-1 not filed, explain why:

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission

Company Representative authorized to supervise plugging operations: THOMAS LARSON

Address: 562 WEST STATE ROAD 4 City: OLMITZ State: KS Zip: 67564 + 8561  
Phone: (620) 653-7368

Plugging Contractor License #: 99996 Name: ALLIED CEMENTING COMPANY

Address 1: P.O. BOX 31 Address 2: \_\_\_\_\_

City: RUSSELL State: KS Zip: 67665 + 31

Phone: 785-483-2627

Proposed Date of Plugging (if known): UPON APPROVAL

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 4/13/2009 Authorized Operator / Agent: \_\_\_\_\_

*Thomas Larson*  
(Signature)

Dist 4  
199

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

LARSON ENGINEERING, INC. DBA LARSON OPERATING  
562 W STATE RD 4  
OLMITZ, KS 67564-8561

April 20, 2009

Re: POLCYN A #1  
API 15-167-23140-00-00  
10-14S-15W, 1320 FSL 1980 FEL  
RUSSELL COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

**This notice is void after October 17, 2009. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.**

District: #4  
2301 E. 13th  
Hays, KS 67601  
(785) 625-0550

Sincerely,

Steve Bond  
Production Department Supervisor