

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15 - 007-22,252 - 00-01 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued,

indicate original spud or completion date 7-29-89.

Well Operator: F.G. HOLL COMPANY L.L.C. KCC License #: 5056  
(Owner / Company Name) (Operator's)

Address: 9431 E. Central Suite #100 City: Wichita

State: Kansas Zip Code: 67206 Contact Phone: ( 316 ) 684 - 8481

Lease: Lambert OWWO Well #: 1-4 Sec. 4 Twp. 30 S. R. 13  East  West

NE - SW - SE Spot Location / QQQQ County: BARBER

990 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

1650 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well

SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: 10 3/4 Set at: 265' Cemented with: 235 Sacks

Surface Casing Size: 8 5/8" Set at: 1004' Cemented with: 230 Sacks

Production Casing Size: 4 1/2" Set at: 4718' Cemented with: 225 Sacks

List (ALL) Perforations and Bridgeplug Sets: (4485,4489,4491.5,4493,4503) (4383-4404')

Elevation: 1868' ( G.L. /  K.B.) T.D.: 4720' PBDT: 4550' Anhydrite Depth: \_\_\_\_\_  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): HEAVY MUD, HULLS, CEMENT AND PLUG ACCORDING TO KCC.

RECEIVED  
KANSAS CORPORATION COMMISSION

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

MAR 26 2009

If not explain why? \_\_\_\_\_ CONSERVATION DIVISION  
WICHITA KS

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: ROB LONG

Address: P.O. BOX 158 Phone: ( 620 ) 793 - 0915

City / State: BELPRE/KANSAS

Plugging Contractor: QUALITY WELL SERVICE KCC License #: 31925

Address: 190 US HIGHWAY 56 ELLINWOOD/KANSAS Phone: ( 620 ) 727 - 3410  
(Company Name) (Contractor's)

Proposed Date and Hour of Plugging (if known?): \_\_\_\_\_

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 3/18/2009 Authorized Operator / Agent: Adam Thom (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Dist 1  
PT

# STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

oww

WELL LOG ----- LAMBERT #1-4  
NE SW SE, Section 4-T30S-R13W, Barber County, Ks.

OWNER: F. G. Holl

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: July 29, 1989

COMPLETED: August 9, 1989

TOTAL DEPTH 4720'

## LOG

0' - 130' surface soil and sand  
130' - 267' red bed  
267' - 620' shale & redbed  
620' - 1019' shale  
1019' - 4720' lime & shale

## CASING RECORD

Ran 6 joints 10 3/4" 32.30# new casing.  
252.31' pipe set at 265' KB. Cemented  
with 235 sacks 60/40 Pozmix, 2% Gel, 3%  
cc. Plug down at 6:00PM 7-29-89  
by Howco - good returns.

Note: lost circulation at 853', spotted  
150 sacks at 853' and 100 sacks at 822'.

Ran 28 joints 8 5/8" 23# new casing.  
989.39' pipe set at 1000' KB. Cemented  
with 230 sacks 60-40 Pozmix, 2% gel and  
3% cc. Plug down at 5:30PM 7-31-89  
by Howco - no returns.

Ran 131 joints 4 1/2" 10.5# used casing.  
4710.39' pipe set at 4718' KB. Cemented  
with 100 sacks Lite followed with 125  
sacks 50/50 Pozmix W/ regulare F. G.  
Holl additives. Plug down at 4:30 PM  
8-9-89 by Howco. Centralizers on jts.  
1, 4, & 15. Scratchers 4480'-4520';  
4360' - 4470'. Shoe joint 15.58' long.

## DEVIATIONS

597' 3/4°  
4330' 3/4°

RECEIVED  
KANSAS CORPORATION COMMISSIONER  
MAR 26 2009  
CONSERVATION DIVISION  
WICHITA, KS



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

HOLL, F.G., COMPANY L.L.C.  
9431 E CENTRAL STE 100  
WICHITA, KS 67206-2563

April 21, 2009

Re: LAMBERT OWWO #1-4  
API 15-007-22252-00-01  
4-30S-13W, 990 FSL 1650 FEL  
BARBER COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

**This notice is void after October 18, 2009. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.**

Sincerely,

Steve Bond  
Production Department Supervisor

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(620) 225-8888