

15-195-19038-00-00

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
3-13-1962
MAR 1 1962
CONSERVATION DIVISION
WICHITA, KANSAS

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. APPROX CEL OF NW 1/4 County: Trego
Location: 1320' S of N line & 880' W of E line
of NW 1/4 Sec. 26 Twp. 11 Rge. (E) (W) 23
Name of Field: _____ Total Depth: 3654

I have this date completed supervision of plugging of:
Lease Name: ~~Holscomb~~ ~~Holscomb~~ ~~Holscomb~~ ^{ES 3/11/09} HOLCOMB Well No. 1

Operator's Full Name: Fred Hambright

Complete Address: 915 Union Center Wichita, Kansas

Plugging Contractor Knight Casing Pulling Co

Address: Chase, Kansas License No. 436

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated; _____

Was any delay in plugging operations caused by Conservation Division Agent?
Yes _____ No

If Yes how long? _____ Reason: _____

Operation Completed: Hour 6:30PM Day 8 Month 3 Year 62

The above well was plugged as follows:

15" 167' circulated with cement - 8 5/8" 3639' with 570 sax cement.
Sand to 3620', set 5 sax cement - pulled 810' 8 5/8" to 500', circulated
hole with heavy mud through 8" (75 sax Gel), displaced 25 sax cement through
8 5/8" at 500', heavy mud to 150', displaced 25 sax cement through 8 5/8" at
150', heavy gel mud to 20', set 15 sax cement to bottom cellar.
Mudding and cementing by Knight Company Pump Truck.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 3/19/62
INV. NO. 4683-W