

15-195-20050-00-00

KANSAS

Form CP-3  
Rev. 6-9-67

*Y*  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
12-14-1967  
DEC 14 1967

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

CONSERVATION DIVISION  
KANSAS

Operator's Full Name Okmar Oil Company,

Complete Address 1130 Wichita Plaza, Wichita, Kansas.

Lease Name Howat Well No. 1

Location NW-NW-NW Sec. 26 Twp. 11 Rge. (E) (W)23

County Trego Total Depth 3900'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Leben Drilling, Incorporated,

Address Box #486, Great Bend, Kansas. License No.       

Operation Completed: Hour 1:45 AM Day 10 Month 12 Year 1967

The above well was plugged as follows:

230'--8 5/8" Surface pipe, cement circulated with 165 Sx.  
Dakota section from 755' to 950'.

Circulated hole with heavy mud. Pulled DP to 975' and displaced 100 Sx. cement thru  
DP from 975' to 655'. Pulled DP to 240' and displaced 20 Sx. cement thru DP from  
240' to 180'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *M. A. Nichols*  
Well Plugging Supervisor

DATE 12/14/67

INV. NO. 6912-W