

15-195-20090-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 24 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Beacon Resources Corporation,

Complete Address: 312 Union Center Building, Wichita, Kansas.

Lease Name Garrett Well No. 1

Location NW-NE-NE Sec. 27 Twp. 11 Rge. (E) (W) 23

County Trego Total Depth 3920'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: L. J. Dreiling & Sons, Incorporated,

Address: Victoria, Kansas, License No.

Operation Completed: Hour 7:15PM Day 22 Month 10 Year 1968

The Above well was plugged as follows:

211'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 775'.

Circulated hole with heavy mud. Pulled DP to 1000' and displaced 100 Sx. cement thru
DP from 1000' to 675'. Pulled DP to 240' and displaced 20 Sx. cement thru DP from
240' to 180'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 10/24/68
INV. NO. 8692-44

Signed: M. L. D. [Signature]
Well Plugging Supervisor