

15-195-20028-00-00

KANSAS

Form CP-3
Rev. 6-26-62

Y

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
7-31-1967
JUL 31 1967
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Beacon Resources Corporation,

Complete Address: 412 Union Center, Wichita, Kansas,

Lease Name Rhoades Well No. 1

Location SW-NE-SW Sec. 35 Twp. 11 Rge. (E) (W) 23

County Trego Total Depth 3941'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: L. J. Dreiling & Sons, Incorporated,

Address: Victoria, Kansas. License No. _____

Operation Completed: Hour 7:00PM Day 24 Month 7 Year 1967

The Above well was plugged as follows:

165' --8 5/8" Surface pipe, cement circulated with 100 Sx.
Dakota section from 1400' to 1600'.

circulated hole with heavy mud, set plug thru DP from 1625' to 1300'
with 100 Sx. cement. Pulled DP to 180' and set plug thru DP from 180'
to 120' with 20 Sx. cement. Pulled DP, filled hole with heavy mud to
40', set bridge with 1/2 sack hu&ls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *A. L. Nichols*
Well Plugging Supervisor

DATE 9/31/67
INV. NO. 6043-U