

15-195-20143-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 17 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Landes Exploration Company & Sentinel Resources Corporation,

Complete Address P. O. Box #867, Magnolia, Arkansas.

Lease Name Ott Well No. 2

Location SW-NE-SE Sec. 3 Twp. 11 Rge. (E) (W) 24

County Trego Total Depth 3940'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Hellar Drilling, Incorporated,

Address 339 Union Center Building, Wichita, Kansas. License No.

Operation Completed: Hour 3:45 AM Day 15 Month 11 Year 1969

The above well was plugged as follows:

207'--8 5/8" Surface casing, cement circulated.
Top of Dakota section @ 765'.

Circulated hole with heavy mud. Pulled DP to 990' and displaced 100 Sx. cement thru
DP from 990' to 665'. Pulled DP to 215' and displaced 20 Sx. cement thru DP from
215 to 155'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 11/17/69
INV. NO. 853-W