

15-195-20210-00-00

Form CP-3  
Rev. 6-4-68

KANSAS

*4*  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
4-11-1972  
APR 11 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name A. Scott Ritchie and John Graves,

Complete Address 412 Union Center, Wichita, Kansas.

Lease Name Geyer Well No. 1

Location CE/2-SE-NW Sec. 3 Twp. 11 Rge. (E) (W) 24

County Trego Total Depth 3940'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Dreiling Oil, Incorporated,

Address R. R. #2, Victoria, Kansas. License No.       

Operation Completed: Hour 3:30 PM Day 5 Month 4 Year 1972

The above well was plugged as follows:

210'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 775'.

Circulated hole with heavy mud. Pulled DP to 900' and displaced 110 Cu. Ft. cement  
thru DP from 900' to 675'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru  
DP from 245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/13/72

INV. NO. 5537-107

Signed: K. L. Nichols  
Well Plugging Supervisor