

15-195-20065-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
6-12-1972
JUN 12 1972
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Dreiling Oil, Incorporated,

Complete Address R. R. #2, Victoria, Kansas.

Lease Name Littlechild Well No. 4

Location SE-NW-NW Sec. 13 Twp. 11 Rge. (E) (W) 24

County Trego Total Depth 3975'

Abandoned Oil Well Gas Well Input Well SWD Well X D & A

Other well as hereafter indicated

Plugging Contractor Russ Casing Pulling, Incorporated,

Address Box #1082, Great Bend, Kansas. License No. 623

Operation Completed: Hour 4:00 PM Day 7 Month 6 Year 1972

The above well was plugged as follows:

170'--8 5/8" Surface casing, cement circulated with 125 Sx.
3974'--4 1/2" casing cemented on bottom with 200 Sx. Top of perforations from 3586' to 3588'.

Sanded well back to 3500' and set 4 Sx. cement with dump bailer. Pulled 4 1/2" casing (1650') and squeezed well initially with 5 sacks hulls and 12 sacks gel and followed with 110 Cu. Ft. cement from 950' to 625' then 11 sacks gel from 625' to 185' and followed with 30 Cu. Ft. cement from 185' to 110' then 2 sacks gel from 110' to 30' and finally 10 Cu. Ft. cement from 30' to bottom of cellar. Maximum pump-in pressure-300#. Final shut-in pressure-100#. (Mudding and cementing by Allied).

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED
DATE 6-13-72
INV. NO. 5851-W