

15-195-20009-00-00

KANSAS

Form CP-3

Rev. 6-9-67

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
2-8-1968  
FEB 8 - 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Leo J. Dreiling Oil Company,  
Complete Address Victoria, Kansas.  
Lease Name Littlechild Well No. 3  
Location CN/2-SE-NW Sec. 13 Twp. 11 Rge. (E) (W) 24  
County Trego Total Depth 3970  
Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A       
Other well as hereafter indicated       
Plugging Contractor Russ Casing Pulling, Incorporated,  
Address Box #1082, Great Bend, Kansas. License No. 623  
Operation Completed: Hour 10:00 AM Day 4 Month 2 Year 1968

The above well was plugged as follows:

168'--8 5/8" Surface pipe, cement circulated with 125 Sx.  
3970'--4 1/2" Production casing cemented with 200 Sx. Well Plugged back to 3939',  
Top perforations @ 3869'.  
Sanded well B ack to 3850' and set 3 Sx. cement with dump bailer. Pulled 4 1/2" casing,  
and squeezed well with initially 12 Sx. gel and followed with 100 Sx. cement from  
1000' to 680', then 12 sacks gel from 680' to 180' and followed with 20 Sx. cement  
from 180' to 120' then 1 sack gel from 120' to 40' and finally 10 Sx. cement from 40'  
to bottom of cellar. Maximum pump-in pressure-200#. Final shut-in pressure-50#.  
Recovered 3012' 4 1/2" casing. (Cementing and mudding operations by Allied Cementing).

I hereby certify that the above well was plugged as herein stated.

Signed: A. L. J. J. J.  
Well Plugging Supervisor

INVOICED

DATE 2/8/68  
INV. NO. 7226-W