

15-195-30166-00-00

Form CP-3  
Rev. 6-4-68

KANSAS

*M*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
6-12-1972  
JUN 12 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Dreiling Oil, Incorporated,  
Complete Address R. R. #2, Victoria, Kansas.  
Lease Name Littlechild Well No. 2  
Location SW-NE-NW Sec. 13 Twp. 11 Rge. (E) (W) 24  
County Trego Total Depth 3920'  
Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A   
Other well as hereafter indicated \_\_\_\_\_  
Plugging Contractor Russ Casing Pulling, Incorporated,  
Address Box #1082, Great Bend, Kansas. License No. 623  
Operation Completed: Hour 3:00 PM Day 7 Month 6 Year 1972

The above well was plugged as follows:

163'--8 5/8" Surface casing, cement circulated with 125 Sx.  
3920'--4 1/2" Production casing cemented on bottom with 125 Sx. Top of perforations from 3851' to 3855'.  
Sanded well back to 3800' and set 4 Sx. cement with dump bailer. Pulled 4 1/2" casing (1850') and squeezed well initially with 5 sacks hulls and 13 sacks gel and followed with 110 Cu. Ft. cement from 900' to 575' then 9 sacks gel from 575' to 215' and followed with 30 Cu. Ft. cement from 215' to 140' then 3 sacks gel from 140' to 25' and finally 10 Cu. Ft. cement from 25' to bottom of cellar. Maximum pump-in pressure-300#. Final shut-in pressure-100#. (Mudding and cementing operations by Allied).

I hereby certify that the above well was plugged as herein stated.

Signed: *N. G. Nichols*  
Well Plugging Supervisor

INVOICED  
DATE 6-13-72  
INV. NO. 5850-W