

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
6-12-1972
JUN 12 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Dreiling Oil, Incorporated,
Complete Address R. R. 32, Victoria, Kansas.
Lease Name Littlechild Well No. 1
Location NE-NE-NW Sec. 13 Twp. 11 Rge. (E) (W) 24
County Trego Total Depth 3935'
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Russ Casing Pulling, Incorporated,
Address Box #1082, Great Bend, Kansas. License No. 623
Operation Completed: Hour 1:00 PM Day 7 Month 6 Year 1972

The above well was plugged as follows:

164'--8 5/8" Surface casing, cement circulated with 125 Sx.
3935'--4 1/2" Production casing cemented on bottom with 125 Sx. Top of perforations from 3845' to 3848'.

Pushed plug to 3800', sanded well back from 3800' to 3775' and set 4 Sx. cement with dump bailer. Pulled 4 1/2" casing (2510') and squeezed well initially with 5 sacks hulls and 13 sacks gel and followed with 110 Cu. Ft. cement from 900' to 575' then 9 sacks gel from 575' to 215' and followed with 30 Cu. Ft. cement from 215' to 140' then 3 sacks gel from 140' to 25' and finally 10 Cu. Ft. cement from 25' to bottom of cellar.

Maximum pump-in pressure-350#. Final shut-in pressure-100#. (Mudding and cementing by Allied Cementing).

I hereby certify that the above well was plugged as herein stated.

Signed: W. G. Nichols
Well Plugging Supervisor

INVOICED

DATE 6-13-72
INV. NO. 5849-W