

State of Kansas



15-195-20028-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
7-31-1967  
JUL 31 1967

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Bob Miller of L. J. Dreiling & Sons has this date requested permission to plug the following described well:

Mr. Miller guarantees payment of the plugging fee.

Operator's full Name: Beacon Resources Corporation,

Complete Address: 412 Union Center, Wichita, Kansas.

Lease Name: Rhoades Well No. 1

Location: SW-NE-SW Sec. 35 Twp. 11 Rge. (E)(W) 23

County Trego Total Depth 3941' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Miller was instructed to plug the well as follows:

165'--8 5/8" surface pipe, cement circulated with 100 Sx. Dakota section from 1400' to 1600'.

Set plug from 1625' to 1300' thru DP with 100 Sx. cement.

Pull DP to 180' and displace 20 Sx. cement thru DP to 120'.

Pull DP, set plug with 1/2 sack hulls and 10 Sx. cement. to bottom of cellar.

Very truly yours,

*H. L. Nichols*

Conservation Division Agent