

State of Kansas



15-195-20030-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
8-21-1967  
AUG 21 1967

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Norman Cook of Abercrombie Drlg. Inc., has this date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: McClure Oil Co. & Abercrombie Drlg. Inc.

Complete Address: 801 Union Center, Wichita, Kansas.

Lease Name: Mary Weber Well No. 1

Location: CSE-NE Sec. 2 Twp. 11 Rge. (E)(W)24

County Trego Total Depth 3940 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Cook was instructed to plug the well as follows:

201'--7" OD Surface pipe, cement circulated with 100 Sx. (6 1/2 hole) Dakota section from 1100' to 1300'.

Circulate hole with heavy mud, pull DP to 1320' and displace 60 Sx. cement thru DP. Pull DP to 210' and displace 15 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 5 Sx. cement to bottom of cellar.

Very truly yours,

W. L. Nichols  
Conservation Division Agent