



15-195-2043-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION
NOV 17 1969
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Warren Davis of Hellar Drilling, Inc., has this date requested permission to plug the following described well:

Mr. Davis guarantees payment of the plugging fee.

Operator's full Name: Landes Exploration Co., & Sentinel Resources Corp.,

Complete Address: P. O. Box #867, Magnolia, Arkansas.

Lease Name: Ott Well No. 2

Location: SW-NE-SE Sec. 3 Twp. 11 Rge. (E)(W) 24

County: Trego Total Depth 3940' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Davis was instructed to plug the well as follows:

207'--8 5/8" Surface casing, cement circulated.
Top of Dakota section @ 765'.

Circulate hole with heavy mud. Pull DP to 990' and displace 100 Sx.
cement thru DP. Pull DP to 215' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent