



15-195-20210-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
4-11-1972  
APR 11 1972

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Draper of Dreiling Oil, Incorporated has this date requested permission to plug the following described well:

Mr. Draper guarantees payment of the plugging fee.

Operator's full Name: A. Scott Ritchie & John Graves,

Complete Address: 412 Union Center, Wichita, Kansas.

Lease Name: Geyer Well No. 1

Location: CE/2-SE-NW Sec. 3 Twp. 11 Rge. (E)(W) 24

County: Trego Total Depth 3940' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Draper was instructed to plug the well as follows:

210'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 775'.

Circulate hole with heavy mud. Pull DP to 900' and displace 110 Cu. Ft. cement thru DP. Pull DP to 245' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

*W. L. Nichols*

Conservation Division Agent