

State of Kansas



15-195-20029-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
CORPORATION COMMISSION
AUG 14 1967
8-14-1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Norman Cook of Abercrombie Drilling Inc has this date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: McClure Oil Co. & Abercrombie Drlg, Inc.,

Complete Address: 801 Union Center, Wichita, Kansas.

Lease Name: Hollandworth Well No. 1

Location: 440'FWL & 2200'FWL Sec. 10 Twp. 11 Rge. (E)(W)24

County Trego Total Depth 3915 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cook was instructed to plug the well as follows:

204'--7" OD Surface pipe, cement circulated with 100 Sx. (6 1/4" hole) Dakota section from 1455 to 1670'.

Circulate hole with heavy mud. Pull DP to 1700' and displace 100 Sx. cement thru DP. Pull DP to 210' and displace 20 Sx. cement thru DP. Pull DP, set bridge @ 40' and 10 Sx. cement to bottom of cellar.

Very truly yours,

H. S. Nichols
Conservation Division Agent