

State of Kansas



15-195-30167-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
12-20-1966
DEC 20 1966

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Bob Miller of L. J. Dreiling & Sons has this

date requested permission to plug the following described well:

Mr. Miller guarantees payment of the plugging fee.

Operator's full Name: Leo J. Dreiling Oil Company,

Complete Address: Victoria, Kansas.

Lease Name: Walker Well No. B-1

Location: SW-NW-NE Sec. 13 Twp. 11 Rge. (E)(W) 24

County Trego Total Depth 3970 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Miller was instructed to plug the well as follows:

168'--8 5/8" Surface pipe, cement circulated with 125 Sx.

Circulate hole with heavy mud, set plug @ 600' and 25 Sx. cement.

"	"	180'	with $\frac{1}{4}$ sk. hulls &
			25 Sx. cement.
"	"	40'	with $\frac{1}{2}$ sk. hulls &
			10 Sx. cement .

Very truly yours,

M. L. Nichols
Conservation Division Agent