



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
6-12-1972
JUN 12 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Russell Sullivan of Russ Casing Pulling, Inc., has this date requested permission to plug the following described well:

Mr. Sullivan guarantees payment of the plugging fee.

Operator's full Name: Dreiling Oil, Incorporated,

Complete Address: R. R. #2, Victoria, Kansas.

Lease Name: Littlechild Well No. 4

Location: SE-NW-NW Sec. 13 Twp. 11 Rge. (E)(W) 24

County: Trego Total Depth 3975' Oil Well

Gas Well Input Well SWD Well X D & A Lost Hole

Mr. Sullivan was instructed to plug the well as follows:

170'--8 5/8" Surface casing, cement circulated with 125 Sx.
3974'--4 1/2" casing cemented on bottom with 200 Sx. Top of perforations from 3586' to 3588'.

Sand well back to 3500' and set 4 Sx. cement with dump bailer. Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 25 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

M. S. Dickels
Conservation Division Agent