

State of Kansas



15-195-20009-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 8 - 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Russell Hoberecht of Russ Casing Pulling, Inc., has this date requested permission to plug the following described well:

Mr. Hoberecht guarantees payment of the plugging fee.

Operator's full Name: Leo J. Dreiling Oil Company,

Complete Address: Victoria, Kansas.

Lease Name: Littlechild Well No. 3

Location: CN/2-SE-NW Sec. 13 Twp. 11 Rge. (E)(W) 24

County Trego Total Depth 3970 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Hoberecht was instructed to plug the well as follows:

168'--8 5/8" Surface pipe, cement circulated with 125 Sx.  
4 1/2" Production casing cemented with 200 Sx. Well plugged back to 3939'. Top perforations @ 3869'.

Sand well back to 3850' and set 3 Sx. cement with dump bailer. Pull 4 1/2" casing and squeeze well with 25 sacks gel and 130 Sx. cement.

Very truly yours,

M. L. Fichels  
Conservation Division Agent