

## 15-195-20293-00-00

## State Corporation Commission

## CONSERVATION DIVISION

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock Administrator 500 Insurance Building Wichita, Kansas 67202 RECEIVED STATE CORPORATION COMMISSION 9-20-1974 SEP 2 0 1974

CONSERVATION DIVISION Wichita, Kansas

Dear Sir:

Mr. Date Bucherste.	of John O. Farmer, incorporated has this
date requested permiss	ion to plug the following described well:
Mr. Bucheister	guarantees payment of the plugging fee.
Operator's full Name:	Mack Oil Company,
Complete Address:	812 Union Center, Wichita, Kansas.
Lease Name:	Littlechild Well No. 2
Location:	SW-SE-SW Sec. 14 Twp. 11 Rge. (E) (W) 24
County:	Trego Total Depth 4060' Oil Well
Gas Well Input Well SWD Well D & A X Lost Hole	
Mr. Bucheister	was instructed to plug the well as follows:
203'8 5/8" Surface casing, cement circulated with 160 Sx.	
Top of Dakota section @	9 800'.
Circulate hole with heavy mud. Pull DP to 1025' and displace 110 Cu. Ft. cement thru DP. Pull DP to 215' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 50' with \( \frac{1}{2} \) sack hulls and 10 Cu. Ft. cement to bottom of cellar.	

Very truly yours,

Conservation Division Agent