



15-195-20218-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
6-6-1972  
JUN 6 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Dale Bucheister of John O. Farmer, Incorporated has this date requested permission to plug the following described well:

Mr. Bucheister guarantees payment of the plugging fee.

Operator's full Name: John O. Farmer, Incorporated,

Complete Address: 370 West Wichita Avenue, Russell, Kansas.

Lease Name: Owens Well No. 1

Location: NW-NW-NW Sec. 15 Twp. 11 Rge. (E)(W) 24

County: Trego Total Depth 3975' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Bucheister was instructed to plug the well as follows:

20 1/2" -- 8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 700'.

Circulate hole with heavy mud. Pull DP to 925' and displace 110 Cu. Ft. cement thru DP. Pull DP to 215' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent